

# CONCRETE AND CONSTRUCTIONAL ENGINEERING

INCLUDING PRESTRESSED CONCRETE

MARCH 1960



VOL. LV. NO. 3

FIFTY-FIFTH YEAR OF PUBLICATION

PRICE 2s.

ANNUAL SUBSCRIPTION 3s. POST FREE. \$3.90 in Canada and U.S.A.

## LEADING CONTENTS

	PAGE
"A Word is Wanted": Report on Competition . . . . .	109
Slabs Spanning in Two Directions Designed by the Yield-line Method By G. M. Mills, B.Sc.Tech., A.M.I.C.E., A.M.I.Struct.E. . . . .	111
Prestressed Road Bridge of 110-ft. Span . . . . .	121
Comparison of Analyses of Helical Stairs By V. A. Morgan, M.Eng., A.M.I.C.E. . . . .	127
Nomograms for the Design of Beams and Slabs by the Load-factor Method.—II. By J. C. Steedman . . . . .	133
A Multiple-story Car Park in Bristol . . . . .	139
Precast Ribbed Floor Slabs . . . . .	141

No. 628

ISSUED MONTHLY

Registered for  
Canadian Magazine Post

**BOOKS ON CONCRETE**

CONCRETE PUBLICATIONS LTD., 14 DARTMOUTH ST., LONDON, S.W.1.

For Catalogue of "Concrete Series" books on  
concrete and allied subjects, send a postcard to:

## INDEX OF ADVERTISERS

A.B. MOULD & CONSTRUCTION CO. LTD.	Page	Page	
ANNEAL & CO. (ENGINEERS) LTD.	xviii	LAJARON ALUMINUM CEMENT CO. LTD.	xxiv, xxv
A.C.E. MACHINERY LTD.	xix	LAWS & SON (STAPLES) LTD.	xxvi
ALLAN, H. P. & CO. LTD.	xxvii	LEEDS OIL & GREASE CO. LTD.	xxv
ANDREWES & CO. LTD.	xxviii	LENSCRETE LTD.	xxv
BEECHY'S ENGINEERING CO.	xxix	LILLINGTON, GEORGE, & CO. LTD.	xxv
BEVENS, Wm., & SONS LTD.	xxix	LIND, PETER, & CO. LTD.	xxv
BIGGAWAY FOUNDATIONS & CONSTRUCTION LTD.	xxix		
B.R.C. ENGINEERING CO. LTD.	xxix		
BRENTON STEEL PILING CO. LTD.	xxix		
BYRD, A. A., & CO. LTD.	xxix		
CAPLIN ENGINEERING CO. LTD.	xxxi	McCALL & CO. (SHEFFIELD) LTD.	xxxi
CEMENT MARKETING CO. LTD.	xxxi	MCALLEN MACALLOV LTD.	xxxi
CEMENT & STEEL LTD.	xxxi	MCKINNEY FOUNDATIONS LTD.	xxxi
CHAPMAN, H. W. LTD.	xxxi	MAY & BUTCHER LTD.	xxxi
CHEMICAL BUILDINGS PRODUCTS LTD.	xxxi	MICAHITE & INSULATORS CO. LTD.	xxxi
CHERTHAM & NIELSEN LTD.	xxxi	MILBART FLOORS LTD.	xxxi
CHESTERFIELD, ALICE J., LTD.	xxxi	MILLARD MACHINERY CO. LTD.	xxxi
COCHRANE, JOHN, & SONS LTD.	xxxi	MILLS SCAPFOLD CO. LTD.	xxxi
COLCRETE LTD.	xxxi	MORR, A., & CO. LTD.	xxxi
COLVILLES LTD.	xxxi	MORAN, WHITLEY, & CO. LTD.	xxxi
COMPACTORS ENGINEERING LTD.	xxxi	MULCASTER, Wm., & CO. (CONTRACTORS) LTD.	xxxi
CONCRETE PILING LTD.	xxxi		
CONCRETE PROOFING CO. LTD.	xxxi		
CONCRETE PUMP CO. LTD.	xxxi	P.S.C. EQUIPMENT CO. LTD.	xxxi
CONCRETE SERVICES LTD.	xxxi	PASHLEY & TRICKETT LTD.	xxxi
CONVEYANCE & CO. LTD.	xxxi	PONTASIO LTD.	xxxi
CORNELLY EQUIPMENT CO. LTD.	xxxi	POWELL DUFFY'S TIMBER INDUSTRIES LTD.	xxxi
D.A. MODELS LTD.	xxii	PROSTRENNING SALES LTD.	xxxi
DAVENDON PAPER SALES LTD.	xxii	PROSTRENNING LTD.	xxxi
DICKENS, STUART B., LTD.	xxii	PUMPCRAFT HIRE CO. LTD.	xxxi
DORMAN LONG & CO. LTD.	xxii	PYFORD LTD.	xxxi
ENGINEERING DESIGN & CONSTRUCTION LTD.	xxii		
EVANS LTD.	xxii		
EXPANDITE LTD.	xxii		
FED (GREAT BRITAIN) LTD.	xi		
FLEXIBLE DRIVE & TOOL CO. LTD.	xi		
FORD MOTOR CO. LTD.	xi		
FRANKPILE LTD.	xi		
G.K.N. REINFORCEMENTS LTD.	xxviii	SAMUEL & SON LTD.	xxviii
GLEESON, M. J. (CONTRACTORS) LTD.	xxviii	SAWYER SHELDON LTD.	xxviii
GUINITE CONSTRUCTION CO. LTD.	xxviii	SEALOCRETE PRODUCTS LTD.	xxviii
HILL, RICHARD, LTD.	xxviii	SIMAK-CARVER LTD.	xxviii
HILTON GRAVEL LTD.	xxviii	SIMPLEX CONCRETE FRAMES LTD.	xxviii
HOLLAND & HARRIS AND CUNNIN (Gt. BRITAIN) LTD.	xxviii	STERLIS LTD.	xxviii
HOLST & CO. LTD.	xxviii	STENT PRECAST CONCRETE LTD.	xxviii
HUNTER & SPARKE LTD.	xxviii	STIC B PAINT SALES LTD.	xxviii
IMPERIAL CHEMICAL INDUSTRIES LTD.		STONE COURT BALLAST CO. LTD.	xxviii
JOHNSON, RICHARD, & NEPHEW LTD.	xxviii	STONER, Wm. T., & CO. LTD.	xxviii
JONES, T. C., & CO. LTD.	xxviii	STRENGING DEVELOPMENTS LTD.	xxviii
KRAKER-CARLWOOD & CO. LTD.	xxviii	STUART'S GRANULATORS CO. LTD.	xxviii
KING, J. A., & CO. LTD.	xxviii		
LAJARON VIBRULUM LTD.		TANAG VIBRULUM LTD.	xxviii
TECHNICAL PAINT SERVICES		TECHNICAL PAINT SERVICES	xxviii
TRIMSHAM LTD.		TRIMSHAM LTD.	xxviii
TRITON BAR CO. LTD.		TRITON PLYWOOD MANUFACTURERS LTD.	xxviii
TRITON GRAVELS LTD.		TRITON GRAVELS LTD.	xxviii
TUNNEL PORTLAND CEMENT CO. LTD.		TUNNEL PORTLAND CEMENT CO. LTD.	xxviii
VOLKMAR, O. A.			
WALKER WRIGHT & CO. LTD.			
WALNICK TRADING CO. LTD.			
WESTWOOD, JAMES, & CO. LTD.			
WHITEHEAD IRON & STEEL CO. LTD.			
WHITLEY MORAN & CO. LTD.			
YORKSHIRE HENKEMANS CONTRACTORS CO. LTD.			

# 1½ MILLION CUBIC YARDS OF CONCRETE HAVE BEEN AIR-ENTRAINED WITH FEBCRETE A.E.A.

ON BRITISH GOVERNMENT CONTRACTS  
DURING THE PAST TWO YEARS

FEBCRETE Air-Entraining Agent without adding to cost improves the flowability and workability of concrete, allows the water-cement ratio to be reduced and increases resistance to the passage of water and to repeated cycles of freezing and thawing.

It ensures that full compaction and maximum compressive strength are obtained without excessive vibration, reduces segregation of the aggregates and prevents bleeding. Write for brochure.

**FEB (GREAT BRITAIN) LTD**

LONDON : 102 Kensington High Street, W.8.

Telephone: WESTern 0444

MANCHESTER : Albany Works, Albany Road, Chorlton-cum-Hardy.

Telephone: CHOrton 1063

# GLASS FIBRE PAN MOULDS FOR FLOORS and shuttering for all in-situ concrete work



Glass fibre is an easily adaptable material for shuttering and moulds for all forms of concrete construction. You can see the concrete through Glass Fibre Shuttering, which enables you to check concrete placing and the concrete cover of reinforcement.

LIGHT AS AIR  
STRONG AS STEEL  
NO STICKING  
FIRM AS A ROCK

## GLASS FIBRE

**Consult**

# **D. A. MODELS • LTD**

108 WOODSTOCK ROAD, LONDON, W.4.

TELEPHONE: CHISWICK 2011

# YORKSHIRE HENNEBIQUE

*Contracting Co. Ltd.*

ESTABLISHED 1904

## CIVIL ENGINEERING CONTRACTORS

HEAD OFFICE :  
**HENNEBIQUE HOUSE**  
**The Mount • York**

*Telephone : YORK 54656 (4 lines)*

*Branch Offices :*

**HULL : 30 WINCOLMLEE. Telephone : Hull 29501**

**LEEDS : ROYDS WORKS, LOWER WORTLEY, LEEDS 12.**



Tel.: UXBRIDGE  
3399

# T.P.S. SHUTTERING and MOULD PAINTS

will make your shuttering and moulds last longer,  
often save the labour costs of repeated mould oil  
application, and are also the cheapest alkali  
primers for general use under paint work


Reduced costs and clean concrete surfaces are always obtained from shutters and  
moulds treated with these paints. Wood grain is filled and sealed against water and  
alkali. Douglas Fir staining eliminated

Ask for the type for YOUR purpose  
**SPECIAL TYPES FOR PLYWOOD,  
STEEL OR CONCRETE SURFACES  
TO SUIT ALL REQUIREMENTS**

PROMPT DELIVERY FROM STOCK!

**TECHNICAL PAINT SERVICES, DEPT. C.C.E.**  
THE PAINT CENTRE — UXBRIDGE — MIDDLESEX

## PROJECT FOR SUPERTANKERS



This illustration of the supertanker berths at Tranmere is reproduced by courtesy of the Mersey Docks and Harbour Board. Construction of the berths is being carried out under the direction of their Engineer-in-Chief.

CONTRACTORS

**PETER LIND & COMPANY LIMITED**  
**LONDON**

**ROMNEY HOUSE, TUFTON STREET, LONDON, S.W.1**  
**TELEPHONE ABBEY 7361**

**Use THE best**

**use HOME-PRODUCED  
LIQUID SULPHITE LYE**

**as a component for**

- WATERPROOFERS
- PLASTICISERS
- RETARDERS

**economical in use**

**competitive in price**

**prompt delivery**

LET US SEND YOU DETAILS

**ANDREWS & CO. LTD.**

33-34 CHANCERY LANE, LONDON, W.C.2.

TELEPHONE: CHANCERY 3013-4

**AND AT MANCHESTER AND EDINBURGH**

---

# Colcrete

FOR  
RECONSTRUCTION  
OF  
**DAMS**

Hendre'r Mur, Gfyfyns,  
Maentwrog, Trawsfynydd

**REFACING OF FOUR DAMS  
IN NORTH WALES**  
**TRAWSFNYDD NUCLEAR  
POWER STATION**

Consulting Engineers :  
Main Contractors :  
Grouting Contractors :

Freeman, Fox & Partners.  
Sir Alfred McAlpine & Co. Ltd.  
The Cementation Co. Ltd.



Refacing in progress on Downstream  
Face of the Trawsfynydd Dam.

★ Colcrete was adopted for this  
work due to its impermeability  
and low shrinkage.

Enquiries to:—

**COLCRETE LTD**

**GUN LANE STROOD KENT**

Telephone: Strood 78431-2-3


Grams: Groutcrete, Rochester

# P.S.C. for all FREYSSINET SYSTEM



## ... CONE ANCHORAGE FREYSSINET POWER EQUIPMENT ...

One of the most recent developments in the Freyssinet system of prestressing has been the introduction of power stressing. An electric or I.C. operated motor driving an hydraulic pump is trailer mounted and the hydraulic circuit has been simplified to only two controls which require the operator's attention. These are mounted on the trailer assembly and the jack is thus completely remote-controlled. The advent of power stressing has increased the rate of tensioning by three or four times that of hand pumping.




## P.S.C. MONOWIRE SYSTEM



### ... P.S.C. ANCHORAGE

The 8/276

P.S.C. "MonoWire" Anchorage illustrated here shows a "Hydrarigid" welded seam-jointed metal sheath which screws into the anchorage. A new type of high-impact plastic cable spacer is also available. These anchorages can be supplied for cables of one to twelve wires.



## P.S.C. MONOWIRE POST-TENSIONING ...

This illustration shows the P.S.C. lightweight single-wire jack stressing one of twelve wires on a 12/276 "MonoWire" anchorage. The jack is available with 4" or 6" extensions, and has a spring return.

# prestressing equipment



## ... P.S.C. GROUTING EQUIPMENT

We have made considerable investigations into the grouting of prestressed cable ducts, particularly with regard to the composition of the grout, its mixing and injection. This experience has enabled us to produce trouble-free grout injection pumps, both hand and power operated, designed specifically for cable-duct grouting. The illustration shows the use of hand diaphragm-operated direct-displacement grouting equipment.

## P.S.C. MONOWIRE PRE-TENSIONING . . .

The P.S.C. "MonoWire" pre-tensioning jack illustrated here is available with extensions from 9" to 24". The hand-operated equipment is extended hydraulically and returned pneumatically. The power-operated pump (electric or I.C.) is recommended where a large number of long extensions is anticipated.




## HYDRADUCT SHEATHING FOR PRESTRESSED CONCRETE

This range of sheathing includes "Hydrarigid" and "Hydraflex". It is highly efficient and easy to use, and is strong enough to take the weight of men without damage, yet flexible enough for all normal prestressing requirements. Supplied in standard lengths in diameters from 2" to 4".

## ... BRIDGE BEARING PADS

Illustrated here, has proved its economy and efficiency on over 400 bridge contracts. Each pad is designed specifically for individual requirements from information obtained from a technical questionnaire, on which we ask certain design considerations. Full details are available on request.



## FREYSSI FLAT JACKS . . .

Freyssi Flat Jacks are hydraulic jacks of unusual and unconventional design, which permit enormous forces to be exerted or regulated where the movement required is small. They have applications in underpinning, levelling and thrust control in engineering structures.



# P S C




EQUIPMENT LTD

HEAD OFFICE AND WORKS: ARUNDEL ROAD, INDUSTRIAL TRADING ESTATE, UXBRIDGE, MIDDX

Telephone: Uxbridge 5242


PIONEERS OF PRESTRESSED CONCRETE IN GREAT BRITAIN

for  
bars  
from  
 $\frac{1}{4}$ " to 2"  
dia.



# BAR-BENDING

## with accuracy·speed·economy



**ARD-50  
MODEL**  
ELECTRIC  
OR  
ENGINE DRIVEN

The ARD-50 Model, illustrated above, has an automatic control which permits the desired bending angle to be pre-set, greatly facilitating repetition bending. The bottom illustration shows the bending of an angle loop in one operation. This model is also fitted with a backrest for multiple bending of small diameter bars. We also supply, at extra cost, a special device for bending Hoops and Spirals, and formers and backrests for special steel such as "Square Grip," "Twistee," and "Tentor," etc. This model is complete with standard accessories for bends on a 4D basis, and can be fitted with Electric motor, Air-cooled Petrol engine or Air- or Water-cooled Diesel engine. Our range of bending equipment also includes the RAS40 model for bending bars up to 1½ in. diameter. Both models are available for sale or hire. Full details will be sent on request.

**CEMENT & STEEL, LTD., SECOND AVENUE, CHATHAM, KENT.**

Telephones : Chatham 45580.

Telegrams & Cables : Cambelgi, Chatham.

For  
the  
design  
and  
erection  
of  
concrete structures

Part of the biggest multi-storey  
development outside London.  
11 blocks of 10-storey flats for the  
City of Leeds Housing Committee

Architect  
The Late R. A. H. Livett, Esq.,  
O.B.E., A.R.I.B.A.  
Leeds City Architect



consult

**Concrete Services Ltd**

OUSE ACRES  
BOROUGHBRIDGE ROAD  
YORK  
Telephone 78471 (5 lines)



# INSEPARABLE from REINFORCEMENT

... OF COURSE!

and a guarantee that  
the specified concrete cover  
is accurately maintained . . .

Complying in ALL respects to the British Standard & Codes of Practice. The U-KLIPON BAR SPACER of revolutionary design is instantly fixed with a vice-like grip in the desired position on all types of reinforcement, including mesh and prefabricated. As an inseparable part it positively cannot be displaced by heavy tamping or vibrating. For any Bar Spacing problem,

## CONSULT

## THE B.E.C. BAR SPACER SERVICE

which has been and is responsible for the most outstanding and prominent contribution to accurate bar spacing in reinforced concrete, thus providing precision, economy, and labour-saving means of ensuring that the specified concrete "cover" is maintained under all conditions. It is noteworthy that such is the increasing popularity and demand for "B.E.C." Bar Spacers, borne out by sales in excess of 35 millions, that we are able to RETAIN OUR PRICE LIST OF 1945 WITHOUT MODIFICATION. Over 120 stock sizes of bar spacers enable us to give immediate attention to requirements.

Write now for comprehensive details and samples. Our Technical Consultants will call on request.

Patent Nos. 597,505, 715,563, 789,018, 818,538.

Registered Nos. 870,560, 886,239. English and foreign patents pending.



## B.E.C. BEARER BLOCK FOR GROUND BEAMS • BARREL ROOFING BRIDGES • MAT WORK • ETC.

The "B.E.C." precision-made bearer block is another inexpensive B.E.C. aid to obtain accuracy with speed in concrete construction. Let us send you full details.

Enhance your Prestige.  
Specify and use with  
confidence.

BERRY'S ENGINEERING CO.

SOLE MANUFACTURERS:

Middle Road, Shoreham-by-Sea, Sussex

Phone and Grams: Shoreham-by-Sea 3541-3  
CONTRACTORS TO MINISTRY OF SUPPLY, ETC., ETC.

## Wythenshawe Swimming Pool is taking shape


Our illustration shows what it will look like when completed later this year.

Ultra-modern in design and construction, the pool will incorporate a restaurant, a club room and the very latest heating, ventilating and filtration equipment.

The frame and floors will be reinforced concrete and the external surfaces will all be glazed between concrete mullions.

As main contractors, Simon-Carves are making yet another contribution to the campaign for brighter British building. Our comprehensive civil engineering contracting service is at work on schools and colleges, office buildings, mining installations, railway modification schemes and a great variety of industrial plants. We are ready to build to your design or to accept responsibility for every stage of your contract.

# Building



Architect: Leonard C. Howitt,  
M.Arch., D.A. (Manc.),  
Dip.T.P., D.P.A., F.R.I.B.A.,  
M.T.P.I.  
City Architect, Manchester.

BUILDING AND CIVIL ENGINEERING BY

**Simon-Carves Ltd**




CHEADLE HEATH, STOCKPORT

and at CALCUTTA  
SC218

JOHANNESBURG

SYDNEY

TORONTO



### 35-TONS PRECAST BRIDGE SECTION

We illustrate one of the 35-tons sections produced by Anglian Building Products Ltd., of Atlas Works, Lenwade, Norwich, and 67 Jermyn Street, London, W.I., for British Railways L. M. Region. Main Contractors: Leonard Fairclough Ltd.

# WOODEN MOULD

*was produced by*

# MAY & BUTCHER LTD

SPECIALISTS IN TIMBER SHUTTERS AND MOULDS FOR CONCRETE

More and more Contractors and Precast Concrete Makers in all parts of the country are taking advantage of the first-class service we offer in the supply of timber shutters and moulds to any design and size. This service has proved over and over again that by ordering your shutters and moulds from us you effect every possible saving in time, labour and money. However intricate the shutter or mould, you are assured of accuracy in every detail and a product with long trouble-free life. Shutters and moulds can be supplied with a plastic lining if desired. Full details of this class of work carried out by us are available on request.

HEYBRIDGE BASIN, MALDON, ESSEX.

TELEPHONE: MALDON 698/9



**110-FEET SPAN  
PRESTRESSED BRIDGE  
FOR  
KENT COUNTY COUNCIL**


JOHN

**COCHRANE**


& SONS LTD

**CIVIL ENGINEERING CONTRACTORS**

**POYLE ROAD, COLNBROOK, BUCKS. Tel: Colnbrook 2544**



*Architects :*  
**S. N. Cooke & Partners**  
 F.R.I.B.A.  
*Main Contractors :*  
**William Townson & Sons**  
 Ltd., Bolton.



**Maxweld reinforces it**



The reinforcement fabric used in the Metal Box Company factory at Bolton was supplied by Richard Hill. Do you need reinforcements? Then call up the Maxweld man! He can give you all the facts on the type and quantity of fabric you'll need plus a rough idea of the cost.

And he's backed by the

**Richard Hill Design Service**

who can then draw up more detailed plans and estimates. You can get him at Middlesbrough (2206), London (Mayfair 3536), Birmingham (Mid. 5625), Manchester (Central 1062), Leeds (2-7540), Bristol (24977), Glasgow (Central 1219), Nottingham (Bulwell 27-8383), Bournemouth (Westbourne 63491), Cardiff (46562), Belfast (29126).

## **Maxweld fabric**

is manufactured by **RICHARD HILL LIMITED** (Established 1868)

**Newport Wire and Rolling Mills, Middlesbrough, Yorkshire. Tel: Middlesbrough 2206**

A MEMBER OF THE FIRTH CLEVELAND GROUP



GB6 2116X

**FRANKIPILE**



**Large  
Diameter  
Bored  
Piles**

FOR ALL TYPES  
AND TERRAINS  
AND SOILS  
LITERATURE  
UPON REQUEST

# RECORD

fully  
automatic  
and rapid

# BAR BENDER



## THE SMALL MACHINE WITH A BIG OUTPUT

We illustrate here a machine that will cater for all bending requirements for bars up to 1½ in. in diameter, with accuracy and with unskilled labour. Bending angle is pre-set on a large dial for accuracy and repetition. Clockwise or anti-clockwise bends on the same bar can be made without reversing. Foot or hand control. Please ask for illustrated leaflet No. 47CE.

**CORNELLY EQUIPMENT CO. LTD**

39 VICTORIA STREET


LONDON S.W.1

Telephone: **Abbey 5702-3.** Cables: **Cornelly, London.** Telegrams: **Cornelly, Sowest, London.**

# Coal conveyor trestles and tunnels

for North Thames Gas Board  
at Beckton Gas Works

ENGINEERS North Thames Gas Board London S.W.



50 ft. high trestles and  
tower with 450 ft. long  
x 12 ft. high hyperbolic  
tunnel in reinforced concrete  
and carried on prestressed  
piles.

**Concrete Piling Ltd**

CIVIL ENGINEERING CONTRACTORS

10 WESTMINSTER PALACE GARDENS  
ARTILLERY ROW LONDON S.W.1.

PHONE: ABBEY 1626/7

KEEP IT DRY WITH  
 'PUDLO' EXTERNAL  
 BRAND  
 WATER REPELLENT\*

THE RANGE  
OF 'PUDLO' PRODUCTS  
INCLUDES:

WATERPROOF CEMENT PAINTS  
EXTERNAL WATER REPELLENT  
CEMENT PAINT PRIMER  
CEMENT WATERPROOFING POWDER  
CEMENT BONDER  
PLASTER BONDER  
MORTAR PLASTICISER  
AND FEUSOL FIRE CEMENT

Write for full particulars, including the name of your nearest Ironmonger or Builders' Merchant stocking 'Pudlo' Brand Products to the makers:

KERNER-GREENWOOD & CO. LTD.  
KING'S LYNN, NORFOLK

TELEPHONE: KING'S LYNN 3293

\* 'Pudlo' Brand External Water Repellent is manufactured by the makers of the famous 'Pudlo' Brand Cement Waterproofer, which has been used and accepted as the leading Cement Waterproofer by the Building Industry all over the world for more than fifty years.


'Pudlo' Brand External Water Repellent is colourless and is entirely suitable for weatherproofing the external surfaces of all types of buildings, including houses, flats, agricultural buildings, offices, factories, public buildings, etc. Amongst its many advantages are the following:

- \* It will repel extremely heavy rainfall.
- \* It minimises efflorescence. When efflorescence is severe and continuous, the source of the moisture penetrating into the body of the wall should be traced and eliminated before applying the Repellent.
- \* It retards frost spalling, cracking and disintegration.
- \* It reduces deterioration of interior finishes.
- \* Exterior surfaces are kept freer from dirt and soot.
- \* Surfaces can be painted over if desired after the application of the Repellent.
- \* It may be applied at freezing temperatures provided the surface is dry.
- \* It does not clog the pores and thus allows masonry, bricks, etc. to breathe.
- \* It does not alter the texture, appearance or colour of the surface treated.

PRICES:	1 GALLON . . . . .	32/-
INCLUDING	2 GALLONS . . . . .	62/-
PACKING AND	5 GALLONS . . . . .	150/-
CARRIAGE		


## STRETFORD-ECCLES BY-PASS

**TWELVE**  
 PRESTRESSED CONCRETE  
**BRIDGES**  
 IN LESS THAN  
**SIX MILES**



KINGSBURY CONCRETE COMPANY LTD. USED  
**RYLANDS** HIGH TENSILE  
 STRESS RELIEVED  
**WIRE** IN PRODUCING PRESTRESSED  
 BEAMS FOR THESE BRIDGES

This map shows the route of the STRETFORD-ECCLES BY-PASS and the location of the bridges for which prestressed beams were used. 10 of these bridges are constructed to carry the motorway across roads, road junctions and railways, the other 2 are over bridges.



Map showing the twelve bridges

DEPENDABLE  
 IN THE  
 WORLD OF WIRE

**RYLANDS**

RYLANDS BROTHERS LTD., WARRINGTON, ENGLAND

### The first

1 thick

### **homogeneous fibreboard expansion joint filler**

made in Great Britain

# PD RESILEX

Complies with Air Ministry Specification 20/138 - Part III  
Class 500.

Road and Survey grades of approved paving compounds available on request.

**Standard Sizes**

and 10 AM.

Wedges: From 2" to 4"  
Special sizes and shapes to  
order.

The first British made 100% wood fibre expansion joint fibre manufactured entirely from home produced materials which has many unique advantages wherever concrete is used.

It is impregnated by a new solvent injection process with a low volatile high residual binder guaranteeing saturation of all fibers.

It will not disintegrate when wet because of its water resistance and high water strength.

Roller is not laminated or otherwise fastened together; is unaffected by road and runway grade of mailing compound and can be delivered in pressurized stems. Fully descriptive leaflet on request.



POWELL DUFFRYN TIMBER INDUSTRIES LIMITED

### Queensferry, Chester

Telephone: Hawarden 2001/4




Underreamed boring

**DOWN TO 110 FEET**



with the

**Mc KINNEY**  
**Mobile Rig**




If you would like further details, please write to:

**McKINNEY FOUNDATIONS LIMITED**

Manor Way, Boreham Wood, Hertfordshire. Telephone: Elstree 2854

A **LAING** COMPANY



have been regularly used  
by leading Contractors for  
reinforced concrete work  
since 1903

We were the pioneers in the supply of steel bars for reinforced concrete work and have given to the industry over 50 years of unbroken service, unequalled for quality and dependability. Contracts on which WHITEHEAD STEEL has been used include some of the largest and most important in the country.

We can supply mild steel with an ultimate tensile stress of 28/33 tons to the square inch; medium tensile 33/38 tons to the square inch, and high tensile 37/43 tons per square inch.

We can also supply high tensile bars 40/45 tons to the square inch with a minimum yield of 60,000 pounds per square inch.


WHITEHEAD IRON & STEEL CO. LTD.  
NEWPORT, THE NEWPORT TRAMWAY, MONMOUTHSHIRE, WALES

LONDON OFFICE : Steel House, Tothill Street, S.W.1. Telephone : Whitehall 2984.

BIRMINGHAM OFFICE : King Edward House, New Street, 2. Telephone : Midland 0412 3.

MANCHESTER OFFICE : Chronicle Buildings. Telephone : Blackfriars 1603/4.

GLASGOW OFFICE : 50 Wellington Street, C.2. Telephone : Central 1528.



### Cut out HACKING...

MULSIBOND, the tried and trusted key, will ensure a firm bond no matter how smooth the surface. Suitable for use on concrete, brickwork, glazed tiles, stonework, etc.

## mulsibond

BONDER

for plaster and cement renderings.

### Cut out

### MOULD FACE TROUBLES...

with MOLDCOTE. Brushed or sprayed on, this new liquid treatment provides a smooth polished surface tough enough to withstand damage in everyday use. Will increase the working life of moulds, shuttering or formwork.

## moldcote

SURFACE HARDENER

for moulds and shuttering.

### Cut out

### PRIMING TROUBLES...

by using SURFILM on Asbestos Cement, Hardboard or Bituminised surfaces. After application (just brush on) such difficult materials can be painted any colour.

## surfilm

PRIMER

for difficult surfaces.

PRODUCTS OF



STUART B. DICKENS LTD.

Manor Way, Boreham Wood, Herts.  
Telephone: Elstree 2211

### Cut out this coupon now!

Please send leaflet giving full details of product I have ticked

MULSIBOND  MOLDCOTE  SURFILM

NAME .....

ADDRESS .....

.....

.....

# CHRISTIANI & NIELSEN LTD

## CIVIL ENGINEERS AND CONTRACTORS



Deas Island Tunnel under the Fraser River near Vancouver, officially opened by H.M. Queen Elizabeth on 15th July 1959. This tunnel crossing allows unobstructed passage for ships to Westminster Harbour.

Client: British Columbia Toll Highways and Bridges Authority.  
Design and Construction Management: Christiani & Nielsen of Canada Limited and Foundation of Canada Engineering Corporation Limited.



ROMNEY HOUSE  
TUFTON STREET  
LONDON, S.W.1  
TELEPHONE  
ABBEY 6614/7

A WORLD WIDE ORGANISATION



# CUNITE SPECIALISTS

Expert advice and schemes submitted for cunite work of every kind. Complete information on the various uses of cunite will be gladly sent on request

116 Richmond Road, Kingston-upon-Thames, Surrey. KINGSTON 7883 and 7852  
Telephone:



PIN YOUR FAITH  
TO THE TESTED  
BRAND

THIS LABEL ON  
EVERY BARREL  
CARRIES WITH  
IT FIFTY YEARS'  
EXPERIENCE OF  
MANUFACTURE.

NONE OTHER IS  
"JUST AS GOOD"

THE LEEDS OIL & GREASE CO.

Phone 22480

LEEDS, 10

'Grams: "Grease."



A FIRST-CLASS SERVICE FOR ALL TYPES OF

## **REINFORCEMENT**

DESIGN SUPPLY BENDING AND FIXING OF  
MILD STEEL, COLD WORKED BARS AND  
HIGH TENSILE FABRIC

WE ARE THE SOLE MANUFACTURERS OF

## **COROBAR**

(TRADE MARK)

**THE COLD WORKED BAR  
FOR  
CONCRETE REINFORCEMENT**

**OFFICES :**

ARDSHIEL HOUSE

EMPIRE WAY

WEMBLEY, MDDX.



**WORKS :**

RIGBY LANE

DAWLEY ROAD

HAYES, MDDX.

**THE ENGINEERING DESIGN & CONSTRUCTION  
COMPANY LIMITED**

TELEPHONE: WEMBLEY 9474      TELEGRAMS: EDCON WEMBLEY



# CUT YOUR CONCRETE COSTS

with the

# A.B. MOULD MIXER-DRIVE SHOVEL

ALL-BRITISH DESIGN AND MANUFACTURE

(Patent applied for)

## At last !

The perfect combination of a winch unit attached to and driven by the mixer, but operated from the press-button-controlled shovel.

THE BUILT-IN JIB ELIMINATES  
SITE INSTALLATION COSTS.



LOW CAPITAL OUTLAY RECOVERED IN TEN WEEKS  
NO RUNNING COSTS  
FITTED TO MOST MIXERS

Ask for a demonstration from :

**A. B. MOULD & CONSTRUCTION CO., LTD.**

VULCAN WORKS, VULCAN WAY  
NEW ADDINGTON, SURREY

Telephone : Lodge Hill 2347

Telegrams : Abmould, Croydon

**If you want to pre-tension  
economically and efficiently —  
consult the specialists in this field**

**WIRE AND STRAND GRIPS  
PLAIN AND SPRING-LOADED**

**HYDRAULIC RAMS  
25 TO 200 TONS CAPACITY  
3' TO 36' EXTENSION**

**HYDRAULIC HAND AND  
POWER PUMPS TO SUIT  
ALL RAM SIZES**

**UNIVERSAL PULL-CARRIAGES  
FOR MULTIPLE STRESSING  
IN UNITS OF 50, 100  
AND 150 TONS**


**STRESSING BED DESIGNS  
SUPPLIED FREE WITH ALL  
EQUIPMENT ORDERS  
COMPLETE PLANT LAYOUTS  
UNDERTAKEN BY ARRANGEMENT**

SEND FOR BOOKLET AND PRICE LIST TO


**STRESSING DEVELOPMENTS LTD.**

95 KINGSTON HILL, KINGSTON-UPON-THAMES

TELEPHONE: KINGSTON 2372



## ***Always in the thick of it . . .***



Wherever great constructional projects are in progress . . . wherever the industrial haze is thickest, you will find Land-Rovers at work. You will see them ferrying men and materials about the battle-ground terrain of a building site. You will see them towing loads of castings in the shadow of great rolling mills. You will see them running rings round shunting engines, taking railway lines and pot-holes in their stride. In all fields of Industry, as in the greener fields of agriculture, there's no substitute for the Land-Rover.

*Ask your Distributor or Dealer for a Land-Rover demonstration. Prices from £650.*

***... 4-wheel drive***



*By Appointment  
to Her Majesty Queen Elizabeth II  
Manufacturers of Land-Rovers  
The Rover Co. Ltd.*



Petrol  
or  
Diesel

THE ROVER CO LTD · SOLIHULL · WARWICKSHIRE  
also DEVONSHIRE HOUSE · PICCADILLY · LONDON

CVS-260

**Top quality & service**  
**Site investigations**  
**Bored piling & Foundations**  
**Materials & Structural testing**



— Terresearch's service has proved its worth —

Terresearch specialists have a wide, practical experience in all branches of building and civil engineering, and full resources for carrying out investigations and research and sound speedy construction.

**WE HAVE SUCCESSFULLY CARRIED OUT  
SUCH WORK FOR:**

ATOMIC AND THERMAL POWER STATIONS · AIRFIELD WORKS  
RAILWAY WORKS · BRIDGES · ROAD WORKS  
MARINE AND HYDRAULIC WORKS · MULTI-STOREY OFFICES  
AND APARTMENTS · FACTORIES, etc.

OUR BROCHURE IS YOURS BY REQUEST




BUILDING AND CIVIL ENGINEERING LABORATORY  
PILEING AND FOUNDATION ENGINEERS & CONTRACTORS

RUISLIP ROAD    NORTHLAND    GREENFORD    MIDDLESEX    Telephone: WAXton 6361-2

# WOOD MOULD

for roof-light surrounds for



The mould illustrated above is 10 ft. by 10 ft., and is one of many designed and supplied by us for this contract.

We are specialist mould makers to the concrete industry, and can supply wooden moulds for all types and sizes of precast concrete. Accuracy is guaranteed in every detail and 25-years' experience is always at your service. Many new methods introduced by LAWS & SONS have been adopted by our customers for use in their own shops.

MESSRS.  
WATES LTD

in the  
construction of the

U.S.A.  
EMBASSY  
LONDON

**LAWS**  
& SONS (STAINES) LTD.


(CONTRACTORS TO  
H.M. GOVERNMENT)  
Langley Road Works, Staines,  
Middlesex  
Telephone: Staines 53700



**BOLTS & NUTS**

**TIE-RODS  
ETC.**

**FOR THE  
CONTRACTOR**



*Manufactured by*

**B. PRIEST & SONS LTD. · OLD HILL · STAFFS · ENGLAND**

PHONES: STANLEY HEATH 6227 6 9 & 8220




## Worried about roof waterproofing?

the **EVODE**

### BUILT UP ROOFING SYSTEM

can be applied to any roof

Any roof can be treated \* Permanent waterproofing for large or small roofs \* Applied cold without preliminary treatment \* Used and proved for over 25 years \* Foreman demonstrators are available to assist your own workpeople or, if you prefer, our contracts department can undertake the work for you and provide free maintenance.



A Priming    B Membrane Sandwich  
C Covering    D Black or Coloured Finish

A PRODUCT OF

**EVODE**

OF STAFFORD

ROOF WATERPROOFING · CONCRETE ADMIXTURES AND HARDENERS  
PROTECTIVE PAINTS AND BITUMINOUS COATINGS · GAP AND  
JOINT SEALING MASTICS AND GUNS · INDUSTRIAL ADHESIVES

\* **SEND FOR LITERATURE** Evote Ltd. (Building Chemicals Div.) Stafford. Phone: 2241 (5 lines)  
London Office: 82 Victoria Street, S.W.1, Phone: ABBey 4622 (3 lines)

M.W.154

# “COL-O-ROCK”

Registered Trade Mark

## EXPOSED-AGGREGATE PANELS

by

J. A. KING & CO., LTD

*Write or Phone*

181 Queen Victoria St., LONDON, E.C.4

Telephone: CENtral 5866 (5 lines)

Telegrams: Kinovique Cent London

Best Quality  
**CONCRETE**  
**AGGREGATES**  
*in all grades*

DELIVERED BY ROAD OR RAIL

**WM. BOYER**  
& SONS LTD  
MEMBERS OF S. & G.A. of G.B.  
ESTABLISHED 1810  
IRONGATE WHARF, PADDINGTON, W2  
TELEPHONE : PADDINGTON 3024-8

**SCHMIDT**  
**CONCRETE TEST HAMMER**

for immediate non-destructive determination of compressive strength

**O. A. VOLKMANN, 3 ST. AUGUSTINE'S ROAD, BIRMINGHAM, 16**


Telephone : Edgbaston 1353



# RAWLBOLTS LIFT 5-TON BOULDERS

When wire slinging fails, how do you excavate round granite boulders, weighing five tons or more each, from a pit 12 ft. square and 20 ft. deep? That was the problem in Hong Kong. It was solved by drilling the granite to take a "K" size Rawlbolt fitted with a 1" diameter eyebolt. Says Mr. A. C. Howarth, M.I.C. Project Manager—"This device proved invaluable and lifted boulders up to five tons in weight, even though there was considerable extra load due to suction when we were getting down to the sandbed."

It is this tremendous grip of Rawlbolts that ensures safety in any bolt-fixing job, large or small.



*We are indebted to Messrs.  
George Wimpey & Co. Ltd., the  
Building and Civil Engineering  
Contractors, for the above  
information. The photograph  
was kindly provided by  
Mr. Howarth from the North  
Point Generating Station,  
Hong Kong.*

## Fixed in minutes

Rawlbolts grip by expansion. You drill the material, insert the Rawl bolt, tighten up. The job is ready to take its full load at once—no grouting in, no waiting for cement to harden. A Rawl bolt fixing is made in only a fraction of the time taken by any other method.

*Write now for free technical literature, and file it for quick reference when your next bolt-fixing job turns up.*

### SIZES AND TYPES FOR EVERY PURPOSE

For bolting down machines and heavy plant, use the Loose Bolt Rawl bolt—inserted after the machine is slid into position; for wall-fixings, the Bolt Projecting Rawl bolt. There are Rawlbolts for supporting pipework and for use with pipe hangers, and Hook and Eye Rawlbolts too. Bolt diameters from 1/4" upwards.




# RAWLBOLTS

*For Speed and Strength!*

THE RAWLPLUG CO. LTD.

RAWLPLUG

CROMWELL RD., LONDON, S.W.7



## OUTSTANDING BUILDING . . .

*Outstanding  
products . . .*

**CHEMICAL  
BUILDING  
PRODUCTS  
LIMITED**  
Warble Works  
Cleveland Road  
Hemel Hempstead  
Herts.

**PROLAPIN** Liquid Cement Waterproofer  
**LITHURIN** Concrete Floor Hardener  
**QUICKSOCRETE** P.Q. & D. Rapid Hardeners and  
Setters  
**WETEXI 'S'** Colourless Silicone Waterproofer  
**CONPLAST** Concrete Plasticiser  
**CONPLAST 'W'** Anti-freeze and Plasticiser  
**CEBEX 112** Mortar Improver  
**CEBEX 113** Expanding Grouting Material  
**CEBEX 124** Multi-purpose Slurry Liquid  
**ROAD CONPLAST** Air Entrainer and Plasticiser  
**CONBEX** Plasticised Expanding Grouting Material

## **CHEMICAL BUILDING PRODUCTS LTD**

Telephone: Boxmoor  
4999 (5 lines)  
Telegrams: Prolihu  
Hemel Hempstead

We shall be pleased  
to supply full de-  
scriptive literature.

**LIFTOYL** Floor Cleaner and Degreaser  
**ORKIT & TEKTAM** Bituminous Coatings and  
Compounds  
**CONCURE** Concrete Curing Agent  
**NITOLUX & ROBRITE** Paints



**On the subject of  
PIPES, moulds and  
equipment . . .**



As manufacturers of all types of steel moulds and formwork for precast and in-situ concrete production, we welcome your enquiries in this specialised field.

If required our experienced staff will plan a comprehensive scheme for the manufacture of your precast units on site.

## **Coneybeare**

THE ORIGINAL PIPE MOULDS

CONEYBEARE & CO. LTD., 89-91 Greenwich Church St., London S.E.10 Tel: Greenwich 0821

**concrete  
protection  
during  
construction**

PROMPT DESPATCH  
COMPETITIVE PRICES

# **CHAPMAN'S WATERPROOF CONCRETING PAPER**

conforms to B.S. 1521, Class B, and is available  
at short notice in large or small quantities for  
contracts in any part of the country.


## **AND POLYTHENE ROLLS**

can be supplied in various widths for many  
protective purposes in building work.

**H. W. CHAPMAN LTD, THE EMBANKMENT, WELLINGBOROUGH, NORTHANTS**

TELEPHONE: WELLINGBOROUGH 2214

## Why more and more contractors



**IN BRITAIN** Darex AEA was used throughout in the concrete construction of the Glendevon Dam



**IN BRITAIN** Darex AEA was incorporated in the bulk concrete of the North of Scotland Hydro Electric Board's Allt-na-Lairige Dam

TECHNICAL SERVICE may be obtained from the sole U.K. distributors

\* The first and foremost  
Air Entraining Agent

\* Used in the U.S.A. for  
more than 27 years on  
major projects

\* In use throughout the  
world

Darex AEA is the  
original air entraining  
agent that has proved  
itself throughout the  
world for Dam Con-  
struction, Structural  
Concrete, Roads and  
Aerodromes, Bridges,  
Maritime Works and  
Concrete products.  
America, Belgium,  
Canada, Norway,  
Portugal, Sweden,  
Switzerland and many  
other countries ac-  
claim Darex AEA as  
the first and foremost  
air entraining agent.

**EVODE** OF STAFFORD

Are YOU using the EVODE PERSONAL SERVICE TO DESIGNERS? Write or phone for details.

**EVODE LTD., (BUILDING CHEMICALS DIVISION) STAFFORD Tel: 2241 (5 lines)**



# ask for **Darex AEA**

## as the fifth ingredient for concrete

**DAREX AEA**, a ready-to-use, dark brown liquid, is an aqueous solution of triethanolamine salts of a sulfonated hydrocarbon. For smoother flow and finer finishing, it lubricates the concrete mix with millions of tiny air bubbles. It also contains a catalyst which promotes more rapid and complete hydration of portland cement. Not a resin or by-product, **DAREX AEA** is a chemical formulation manufactured to insure predictable performance. It is harmless and neutral and requires no pre-mixing with corrosive chemicals or water.

**DAREX AEA** is ideally suitable for ready mixed concrete, structural concrete, mass concrete construction, concrete road construction, repairs and patching and concrete products.

- Air bubbles guard against frost damage and cracking even with repeated freezing and thawing.
- Makes concrete resistant to saline solutions, de-icing salts, sulphate and sea waters.
- Less mixing water can be used with no loss in slump.
- Improves placeability.
- Air bubbles lubricate and plasticize the mix.
- Minimizes bleeding, green shrinkage and segregation.
- Catalyst promotes faster and more thorough hydration, thus bringing out more of inherent strength of portland cement; assures greater strength in both lean and rich mixes than non-catalysed air entraining agents.
- Will not entrain excessive air.
- Particularly effective with slag, lightweight or manufactured aggregates that tend to produce harsh concrete.
- Permits use of natural sand deficient in fines.



### Reduce water with **WRDA**

**WRDA**, an aqueous solution of highly purified metallic salts of lignin sulfonic acid, is a ready-to-use, non-setting, dark brown, mobile liquid. It acts as a dispersing and plasticizing agent—makes possible easily placeable mixes with up to 20% less water content and a corresponding increase in strength and durability. It contains a catalyst which counteracts the normal hydration-retarding effect of dispersing admixtures; and a preservative. It is compatible with all known air entraining agents. **WRDA** does not require agitation, it comes ready-to-use.

- **WRDA** reduces natural interparticle attraction of cement grains and makes the mix more workable and placeable with less water.
- Gives low slumps without loss of placeability.
- Makes concrete flow cleanly around reinforcing steel and respond quickly to vibration, spading and compacting.
- Improves water retention and internal cohesiveness of the plastic mix.
- Cuts green and drying shrinkage.
- Reduces bleeding, honeycombing, water gain voids under aggregate and other segregation.
- Allows concrete floors to be finished sooner.
- Increases compressive strength up to 25%; also increases flexural and tensile strengths.
- The action on cement is physical. It does not change the chemical properties.
- Improves appearance of concrete by sharply reducing spalling, leaching and sand streaking.

AIR METERS AND DISPENSERS ARE READILY AVAILABLE

# COPPER STRIPS

## for expansion joints

All Reinforced Concrete Engineers recognise the advantages of using copper strips for sealing joints in concrete work. Copper is ductile, will not crack under repeated bending, is non-corrosive and is unaffected by wet concrete. We specialise in the supply of perforated copper strips of all required lengths and widths for expansion joints, and shall be pleased to submit prices against detailed specification.



DS.14

**ALEX J. CHEETHAM LTD.**

MORTON STREET • FAILSWORTH • MANCHESTER

Telephone: FAILsworth 1115/6



Circular tipping skip 9½ cu. ft.  
to 2 cu. yd.

Bollover skips ½ cu. yd.  
capacity.



Concrete pouring skip side  
discharge 10 cu. ft. to 27 cu. ft.




Bolt skips 3 cu. ft.  
to 7 cu. ft.



Concrete pouring skips bottom  
discharge 10 cu. ft. to 27 cu. ft.



Circular controlled discharge  
bottom dump skips ½ cu. yd.  
to 1 cu. yd.



Skips for tunnelling or trenching  
skips 4-12½ cu. ft. capacity.



Eliminate propping and reduce labour costs with

**MILLS**

**peccco-beam**



**The all-steel horizontal shoring which gives clear spans up to 27' 7"**

- Proven safety factor 2.2:1
- Lightning adjustment from 8' 6" to 27' 7"
- Only two basic parts—easy to erect, store and transport
- Free work areas for kindred trades below
- High load capacity enables larger areas to be shuttered with fewer shores
- Rolled-in camber ensures level slab under load
- Plate section is 'V' shaped, so steel is doubled along length of beam
- Demonstrations arranged
- Immediate delivery from nearest MILLS depot
- Free planning and advisory service

*For lighter loads and clear spans up to 27' 2", use the *Lightweight peccco-beam*.*

For leaflets containing loading tables and full details of Standard and Lightweight PECCO-BEAMS

get in touch with your nearest **MILLS** depot.

**MILLS SCAFFOLD CO. LTD.** (A subsidiary of *Giessi, Keen & Nettlefold, Ltd.*)

*Head Office: Tinsley Works, Hammersmith Grove, London W.6 (Riverside 3011)*

*Depots: BIRMINGHAM • BOURNEMOUTH • BRADFORD • BRISTOL • CANTERBURY • CARDIFF • COVENTRY • CROYDON • EDINBURGH • GLASGOW • HASTINGS • HULL • ILFORD • LIVERPOOL • LONDON • MANCHESTER • MIDDLEBROUGH • NEWCASTLE • NOTTINGHAM • OXFORD • PLYMOUTH • PORTSMOUTH • PRESTON • READING • ROTHERHAM • SOUTHAMPTON • SWANSEA*

**MILLS**



*Bearing points are drop forgings welded to beams. Dowels/bolts to avoid overhanging.*



*Unique wedge-lock recessed at one corner below.*

**THE ~~ME~~ NO LIMIT TO THE SUPPORT YOU CAN GET FROM MILLS**

## Precision in Concrete Cover...



Write Now!

for fully  
illustrated  
brochure

A revolutionary economy  
for lightness, speed of  
handling, and range of  
application—for reinforcing  
bars in concrete.

with **ABIT**  Plastic Distance Pieces

PATENTED. Regd. Design 893503.

**Samuel & Son (moulders) Ltd**

WREN MILL, CHADDERTON, LANCS. Sales Office: Tel: Manchester DEA 4671/2  
Sole Manufacturers and Distributors of ABIT pk Plastic Distance pieces (A.B.  
ABERG No. 31269/58) in Great Britain, The Commonwealth and Eire.

*For faster placing  
and better concrete  
use the*



# HUMDINGER

IMMERSION VIBRATOR

AVAILABLE WITH GRINDING ATTACHMENTS



Here is an immersion vibrator that will cut your concrete-placing costs in a half-dozen ways. High vibrating frequencies of up to 12,000 r.p.m. give stronger concrete and speed up placing—and

you can strike shuttering sooner. At the same time, the 'Humdinger' flexible shafts operate at QUARTER SPEED.

And this means longer life and less maintenance—the drives just keep on running week after week.

Plant records prove that contractors and civil engineers are changing to 'Humdinger' after seeing the difference they can make in concrete placing. Prove it for yourself by using one on your next vibrating job. You can have a 'Humdinger' on trial or hire (with option).



PETROL AND ELECTRIC MODELS AVAILABLE

**ACE MACHINERY LIMITED**

VIBRATOR DEPT., PORDEN ROAD, BRIXTON, LONDON, S.W.2 Telephone: Brixton 3293 (9 lines)

**Buy ACE and you buy RELIABILITY**

BEHIND EVERY JOB...



25 years' experience in  
the scientific repair of  
engineering structures.

**WHITLEY  
MORAN**  
AND CO. LTD  
**GUNITE**  
SPECIALISTS



5 OLD HALL ST, LIVERPOOL, 3  
TELEPHONES: CENTRAL 7975/6  
TELEGRAMS: 'GUNITE' L'POOL 3

*Ensure  
safety  
with*

**DORMAN  
LONG Steel Trench Sheeting**

(Regd. Design No. 850,839)

The ideal for temporary lining,  
easy to drive: can be used over and over again

**PROMPT DELIVERY**

Prices and full particulars on application to

DORMAN LONG (Steel) LTD., SHEET DEPT., AYRTON WORKS, MIDDLESBROUGH  
London Office: Terminal House, 52 Grosvenor Gardens, S.W.1





It is safest to specify STENT!

# STENT

## PRECAST CONCRETE PILEs

Preferred by constructional engineers for their unchanging supremacy, Stent Precast Concrete Piles have proved their qualities wherever used.

**STANDARD SIZES**  
12" x 12" in lengths 15 ft. to 40 ft.  
14" x 14" in lengths 15 ft. to 55 ft.  
Other sizes made to order.

**AVAILABLE FOR IMMEDIATE  
DELIVERY**  
May we forward full details.

**STENT PRECAST CONCRETE LTD.**  
Chequers Lane, Dagenham Dock, Essex. Dominion 0971

Today:

Remember to ask about  
**DURAJOINT** and **DURASEAL** -  
watertight PVC strips for  
expansion and construction  
joints in all concrete  
structures.

Full details and  
descriptive literature from




**THE MICANITE AND INSULATORS CO., LTD.,**

BLACKHORSE LANE, WALTHAMSTOW, LONDON, E.17.

Tel: LARKwood 5500. Grams: Mytilite, London. Telex: 25183



## POWER for industry



Our range of industrial engines are a practical proposition for many types of industrial equipment . . . compressors, cranes, pumps, contracting equipment, earth borers, generators, railcars, welding plant, works trucks, tractors and conversions. Simple design, modern flow-line production methods and common interchangeable parts contribute to the low cost of these high efficiency engines. And remember, every engine is fully backed by a World-wide Parts and Service Organi-

sation. Take your choice from a wide power range . . . Diesel 20 to 86 b.h.p. and Petrol 11 to 87 b.h.p. (12-hr. rating).

**DIESEL ECONOMY**—have you considered the replacement of existing power units in your equipment and trucks with the famous 4D Diesel engine? You'll have the unique advantages of economy, long-life and low running costs . . . plus the best service in the World!

Wherever you are, whatever your problem,



are at your service

For further details of our

### INDUSTRIAL ENGINES

and the equipment they power,  
send the coupon to your nearest Ford Dealer  
or direct to

Please send me technical brochures of your  
\*PETROL/DIESEL Industrial Engines. The  
maximum B.H.P. required is.....at.....  
R.P.M. Also, please send details of the follow-  
ing equipment powered by your engines.

Name.....

Address.....

Nature of Business.....

Telephone No. ....

\* Delete where not applicable

GSI-23-3

*It is* safest to specify STENT!

**STENT**  
**PRECAST**  
**CONCRETE**  
**PILES**

Preferred by constructional engineers for their unchanging supremacy, Stent Precast Concrete Piles have proved their qualities wherever used.

**STANDARD SIZES**  
12' x 12' in lengths 15 ft. to 40 ft.  
14' x 14' in lengths 15 ft. to 55 ft.  
Other sizes made to order.

**AVAILABLE FOR IMMEDIATE DELIVERY**  
May we forward full details.

**STENT PRECAST CONCRETE LTD.**  
Chequers Lane, Dagenham Dock, Essex. Dominion 0971


*Today:*

Remember to ask about DURAJOINT and DURASEAL - watertight PVC strips for expansion and construction joints in all concrete structures.


Full details and descriptive literature from



**THE MICANITE AND INSULATORS CO., LTD.,**  
BLACKHORSE LANE, WALTHAMSTOW, LONDON, E.17.  
Tel: LARKwood 3500. Grams: Mytilite, London. Telex: 25183



## POWER for industry



Our range of industrial engines are a practical proposition for many types of industrial equipment . . . compressors, cranes, pumps, contracting equipment, earth borers, generators, railcars, welding plant, works trucks, tractors and conversions. Simple design, modern flow-line production methods and common interchangeable parts contribute to the low cost of these high efficiency engines. And remember, every engine is fully backed by a World-wide Parts and Service Organisa-

sation. Take your choice from a wide power range . . . Diesel 20 to 86 b.h.p. and Petrol 11 to 87 b.h.p. (12-hr. rating).

**DIESEL ECONOMY**—have you considered the replacement of existing power units in your equipment and trucks with the famous 4D Diesel engine? You'll have the unique advantages of economy, long-life and low running costs . . . plus the best service in the World!

Wherever you are, whatever your problem,



MOTOR COMPANY LIMITED  
ENGLAND

are at your service

For further details of our

## INDUSTRIAL ENGINES

and the equipment they power,  
send the coupon to your nearest Ford Dealer  
or direct to

Please send me technical brochures of your  
\*PETROL/DIESEL Industrial Engines. The  
maximum b.h.p. required is.....at.....  
R.P.M. Also, please send details of the follow-  
ing equipment powered by your engines.

Name.....

Address.....

Nature of Business.....

Telephone No. ....

\* Delete where not applicable

GSI-22-3

LENSCRETE LTD

**maximum light minimum cost**

LITEX roof lights give a very high transmission of light—up to 92%—and are easily and quickly handled and fitted. A full range of standard form metal ventilators, curbs and liners are available for use with LITEX roof lights.

**Litex**

LAMINATED FIBREGLASS  
roof lights

LITEX roof lights with their glass fibre reinforced construction can be used with advantage in many places where conventional lights would be impracticable or too costly. Virtually unbreakable, heavy packing is unnecessary allowing quick and easy handling on site.

LITEX roof lights are ideal for use in schools, hospitals and other buildings where absolute safety is required—they will not shatter and cannot support combustion. The plastic will not creep, nor become brittle with age or very hot temperatures.


LITEX roof lights are not attacked by smoke or fumes from most industrial processes, and may safely be used in factory and workshop buildings.

For further information about LITEX roof lights please write to

LENSCRETE LIMITED Queens Circus London SW8 telephone MACaulay 1063



LITEX spherical roof lights



LITEX rectangular roof lights



LITEX lantern lights

# GUNITE SPECIALISTS

## W.M. MULCASTER

& CO. (CONTRACTORS) LTD.

We invite inquiries for Gunite Linings and Renderings  
for new or old structures of every kind in any part  
of the country.

**HASLINGTON**

Telephone: Crewe 2265-6.

**CREWE**

MODEL  
A.15

1½ IN. DIA.  
ONLY



THE NEW  
AIR  
VIBRATOR

specially designed to cater for  
the compacting requirements of  
low-slump concrete and all  
other designs of concrete mixes

The Model A.15 Air Vibrator, with its high frequency of 12,000 r.p.m. combined with a large amplitude, is a ready and effective answer to the problem of using a vibrator with a small diameter head for compacting a low-slump concrete. It enables the driest of concrete mixes to be thoroughly compacted with the minimum of delay.

The diameter of its head is 1½ in. only. Its weight is 5 lb., and its air consumption 20 cu. ft.

**TEST IT ON YOUR CONTRACT  
WITHOUT OBLIGATION**

The A.15 model is available at short notice for sale or hire. Let us send you full details.

**COMPACTORS ENGINEERING LTD.**


LOCKFIELD AVENUE, BRIMSDOWN, ENFIELD, MIDDX. Telephone: Howard 4063-5

# BRITISH VISQUEEN

*make a No.*

**1**

*choice*



The new British Visqueen factory at Stevenage was built to produce the largest output of polythene sheeting in Europe; and it is here that the Visqueen Building sheet is also manufactured to supply an increasing number of applications for it in the building industry.

To render the concrete factory floors hard, dustless, waterproof and able to withstand exceptionally heavy wear and tear, British Visqueen chose Lillington's No. 1 Metallic Liquid.

For nearly fifty years, architects have specified Lillington's No. 1 Metallic Liquid, the scientifically prepared admixture that renders concrete completely waterproof and dustless and accelerates setting time.

*No. 1 Metallic Liquid is a necessity for waterproofing cement renderings to walls and basements, in mass concrete retaining walls, foundations, flat roofs and tanks. You can rely on it to give complete satisfaction because IT IS THE ONLY PROOFER SOLD UNDER GUARANTEE.*

From **5/-** per gallon

Special terms for  
bulk contracts

Write for Booklet 56

LILLINGTON'S  
**Nº 1 Metallic Liquid**

ALL OUR PRODUCTS NOW SOLD IN FREE CONTAINERS

**GEORGE LILLINGTON & CO. LTD**

Willow Lane, Mitcham, Surrey. Tel: Mitcham 1046. For Scotland: 42 High Street, Greenock.

AP/339A

means 3

MACALLOY

# NEW FREEDOM FOR DESIGNERS

The simplicity and adaptability of Macalloy bars solves many design problems.

There are few fittings, all of them of a robust nature adaptable to any detail.

The small couplers can be located in any section; they permit units to be stressed in lengths and coupled together; they allow one half of a deck to be stressed at a time.

Partial stressing and stressing in stages are simple with rolled threads; restoring or releasing prestress is done in a moment.

Framed structures can be built with simple connections and continuity readily provided.

The positive rolled thread anchorage allows short-length stressing with complete accuracy.

A simple pricing system is available.

Our Engineers are always available to give advice and discuss designs.

## McCALL'S MACALLOY LIMITED

TEMPLEBOROUGH • SHEFFIELD • P.O. BOX 41

Telephone: ROTHERHAM 3074 (P.B. Ex 8 lines)

LONDON: SLOANE 9428  
BIRMINGHAM: ACOCKS GREEN 0329

PORTRUSH: COSSHAM 78792

PRESTRESSING  
STEEL  
by McCALL'S

McCALL & CO. (SHEFFIELD) LTD.

McCALL'S MACALLOY LTD.

PRECISION ROOFS LTD.

McCALL'S MACALLOY (AFRICA) (PROPRIETARY) LTD.

McCALL'S MACALLOY (AUSTRALIA) PTY. LTD.

McCALL'S MACALLOY (CANADA) LTD.

WW

# REINFORCEMENT SERVICE *including* SUPPLY & BENDING

We are manufacturers of mild steel bars for reinforced concrete, and have every facility for supplying bars cut to required lengths. We also bend ready for fixing if desired for contracts in any part of the country. Include our name on your list for future reinforcement requirements.

## WALKER WRIGHT & CO. LTD

DARNALL, SHEFFIELD, 9

TELEPHONE: 41063



Model VP 350-A (Swivel Base or Barrow Mounting)

Prompt Delivery. Highly Competitive Prices. Genuine Service. Re-Sale Terms Available.

\* We operate a 48-hour Shaft Repair Service for all makes. Write to-day for 8-page fully descriptive Catalogue. Agents throughout the world.

30 years' experience in the design and manufacture of flex-shaft tools.

**THE FLEXIBLE DRIVE & TOOL CO., LTD.**

EDENBRIDGE, KENT. Telephone: 3385-6

LONDON OFFICE: 17 QUEENSBERRY WAY, S.W.7. Telephone: KENSington 3583

For Greater Strength, Firmer Bonding  
and Better Surfacing of Concrete

**"BAXTUL"**


Regd. Trade Mark British Made

Extra-High Frequency  
INTERNAL CONCRETE VIBRATORS

● The model illustrated here operates at 9,000 to 15,000 Vibrations per minute from low flexible shaft speeds of 4,500 to 7,500 R.P.M.

● Petrol or Electric Drive.  
● Robustly built throughout and backed by genuine service.  
● Fitted centrifugal clutch, long-life flexible drive and Vibrator.

This unique machine, with quick-change additional tools, can also be used for: SURFACING, WET-RUBBING CONCRETE, GRINDING, DISC SANDING, AND DRILLING (up to 1½" in Concrete, 1" in Steel, and 2" in Wood).



An Electrically Driven PC3 Concrete Pump with remixer. Capacities from 20 to 24 cu. yds. per hour. Ranges actually obtained 135 ft. vertical or 1,500 ft. horizontal. Also smaller model PC4—8-10 cu. yds. per hour.

EFFICIENT RECONDITIONING SERVICE

## CONCRETE BY PUMP AND PIPELINE

- The most efficient method of placing concrete.
- Life of Pump practically indefinite : all essential surfaces in contact with concrete are renewable.
- Pumpable concrete must of necessity be good concrete.
- Pump and Mixing Plant can be located at the most convenient position within the pumping range.
- The continuous output of the Pump at a constant speed governs the working of the whole concreting gang.

THE REGISTERED TRADE MARK OF




THE CONCRETE PUMP COMPANY LIMITED

# THE CONCRETE PUMP COMPANY LTD

4 STAFFORD TERRACE, LONDON, W.8

Telephone Western 3546

Telegrams: Pumperet, Kans, London



In dams of this type—the very hub of extensive hydroelectric schemes—waterstops have a triple function to perform: seepage must be rigorously combatted, movement of concrete mass must be allowed for and future repairs obviated by the waterbars being resistant to corrosion.

As in the case of the dam shown here, Expandite waterstops, whether Rubber or Polyvinyl Chloride, have proved to be unsurpassed in performance where problems such as these have to be taken into consideration. Expandite have also developed an extremely economical Hydrofoil (PVC) having a unique profile: various widths are available.

These form only a section of the complete range of Expandite Products, sufficiently varied to solve joint-filling or sealing problems that occur in any form of constructional undertaking.

The Expandite Technical Service Department offers advice—without any obligation—to architects, civil engineers and builders on all questions of 'joints-that-move!'

## ANOTHER JOINTING PROBLEM SOLVED

**EXPANDITE**  
LIMITED

*Specialists in the manufacture and use of Joint-Fillers,  
Sealing and Waterproofing Compounds, Concrete Additives,  
Anti-Corrosion Treatments & Mechanical Appliances.*  
Chase Rd., London, N.W.10. Tel: ELGar 4321 (14 lines)

Northern Depot: Trafford Park Road, Manchester 17. Eire: Expandite (Ireland) Limited,  
Greenvale Road, Walkinstown, Dublin

ASSOCIATES AND DISTRIBUTORS THROUGHOUT THE WORLD

# REINFORCED CONCRETE DESIGNER'S HANDBOOK

By Chas. E. Reynolds

352 Pages 75 Tables 110 Examples

Revised in accordance with  
British Standard Code 114: 1957

The fifth edition of this handbook is in accordance with the recommendations of the British Standard Code of Practice No. 114 (1957), a special feature being the inclusion of tables and data for use with the ultimate-load method of design. Other improvements and additions have been made to the text and tables dealing with the pressures of granular and cohesive materials, foundations, slabs supported on three or four sides and subjected to triangular loading, loads on bridges, long columns, and the properties of reinforced concrete sections.

#### ORDER FORM

To CONCRETE PUBLICATIONS,  
Ltd.,

14 DARTMOUTH STREET,  
LONDON, S.W.1, England.

Please send ..... copy (copies) of

"Reinforced Concrete Designer's  
Handbook," by Chas. E. Reynolds.

19s. 2d. by post. 4 dollars in Canada and  
U.S.A.

A remittance for ..... is enclosed.

BLOCK CAPITALS PLEASE

NAME .....

ADDRESS .....

.....

.....

Remittances from Canada and U.S.A.  
may be made in the ordinary way by draw-  
ing a check on the customer's bank made  
payable to Concrete Publications, Ltd., in  
dollars and cents or by International Money  
Order.

# RANALAH

for

## STEEL MOULDS



Phone

**BRIGHTON 62216-7-8-9**

for IMMEDIATE ACTION

**RANALAH STEEL MOULDS LTD**  
LOWER BEVENDEAN • BRIGHTON • SUSSEX

FOR THE LONG HAUL  
RELY  
ON

# PLAZCRETE

THE MODERN AID FOR A WELL-DESIGNED CEMENT MIX

**PLAZCRETE RETARDS THE SET**

Permits longer haulage time  
Avoids day joint problems

**PLAZCRETE IMPROVES WORKABILITY AND  
PLASTICITY**

Makes pumping easier  
Saves time placing and vibrating  
Improves consolidation, particularly around  
reinforcement

**PLAZCRETE PERMITS A REDUCED WATER/  
CEMENT RATIO**

Reduces shrinkage  
Eliminates laitance, bleeding and segregation

**PLAZCRETE IN THE MIX REDUCES THE COST  
WITHOUT ANY LOSS OF STRENGTH**

*For further information write to Dept. PC.:*


**SEALOCRETE PRODUCTS LTD.,**  
ATLANTIC WORKS, HYTHE ROAD,  
LONDON, N.W.10.

Telephone : *Ladbroke 0015, P.B.E.*  
Telegrams : *Sealocrete, Wesphone, London.*



# reinforcement

BY PASHLEY & TRICKETT



Give us your bending and delivery schedules and we do the rest. Accurately bent steel reinforcement for all types of concrete construction is delivered on site as and when you want it by our own road transport — each batch clearly identified. All enquiries are dealt with promptly.




**Pashley & Trickett Ltd**

STOKE STREET · SHEFFIELD 9

TELEPHONE: 41136-7

PUMPCRET  
CONCRETE  
PUMP

## THE P.C.4 PUMPCRET CONCRETE PUMP



### CONCRETE BY PUMP AND PIPELINE

#### Specifications:

	Two Sizes	P.C.3	P.C.4
Capacities per hour, approx.	20-24 cu. yd.	20-24 cu. yd.	8-10 cu. yd.
Range:			
Horizontal, approx.	1500 ft.	1250 ft.	
or Vertical, approx.	135 ft.	125 ft.	
Pipeline	6" i.d.	4½" i.d.	
Power required: Electric or Diesel	45 h.p.	25 h.p.	

## FOR HIRE



THE REGISTERED TRADE MARK OF  
THE CONCRETE PUMP COMPANY LIMITED

# PUMPCRET HIRE COMPANY LTD

4 STAFFORD TERRACE, LONDON, W.8

Telephone : Western 3546.

Telegrams : Pumcret, Kens, London

# ALAG

# New!

*A special aggregate for special purposes*

ALAG is a synthetic aggregate which, when used with CIMENT FONDU, PRODUCES CONCRETE WITH THE FOLLOWING UNIQUE PROPERTIES:—



EXTREME RESISTANCE TO ABRASION  
(Hardness of aggregate 7.5 MOHS. Cuts glass)

ENORMOUSLY HIGH STRENGTH IN A MATTER OF HOURS  
(For example 12,000 lb. per sq. inch at 24 hours and 16,000 lb. per sq. inch at 7 days)

HIGH DENSITY  
(167 lb. per cu. ft. air-dried—20 lb. per cu. ft. higher than normal)

HEAT-RESISTANT  
(up to 1150/1200° C.)

OR ALL ABOVE PROPERTIES COMBINED

SHOULD BE USED ONLY WITH HIGH ALUMINA CEMENT (CIMENT FONDU)

*Write for further information. ALAG is available only from:—*

**LAFARGE ALUMINOUS CEMENT COMPANY LIMITED**

73 BROOK STREET, LONDON, W.1. TELEPHONE: MAYFAIR 8546

## Bridge Building—the new way



*Prestressed concrete bridge on Kumeu-Heleenville main highway, North Auckland, New Zealand.*

This is one of over fifty prestressed concrete bridges in New Zealand pioneered by B. & B. Concrete Co. Ltd. using Johnsons wire. Varying in span from 30 ft. to 120 ft., they have drastically cut the costs of bridge building in terms of time, money and traffic interference. Speed was essential on the Kumeu Contract. The first of the beams was delivered to site at the end of October 1955, and the bridge had to be open for the Christmas holidays. For further details write for leaflet.


*Contracting Authority :*  
Ministry of Works, Auckland.

*Design :*  
Pre-stressed Concrete (N.Z.) Ltd.

*Sub Contractors :*  
B. & B. Concrete Co. Ltd.

Johnsons were in at the start with wire for prestressed concrete. Their technicians worked with the Continental pioneers in the development of the technique, and to-day Johnsons wire is specified in a large number of important prestressing contracts.

wire was essential —  
**Johnson**s  
of course!



For compacting mortar cubes  
for compression tests to  
B.S. 12/1958, 146, 1370, 915  
Automatic Time Control

# "CAPCO"

## H.F. VIBRATOR

"CAPCO" CONCRETE TESTING APPARATUS also includes:  
Cube Moulds; Slump Cones; Tensile, Vicat and Cylindrical  
Moulds; Compacting Factor Apparatus—Standard and Auto-  
matic; Sieve Vibrators and Sieves; etc.

### CAPLIN ENGINEERING CO. LTD

ALPAX WORKS, ST. LEONARDS ROAD, WILLESDEN JUNCTION, LONDON, N.W.10  
'Phone: ELGAR 7191. Grams: CAPLINKO, London, N.W.10. Cables: CAPLINKO, LONDON

WATERTIGHT  
LININGS  
FOR  
RESERVOIRS,  
SWIMMING  
POOLS, ETC.



LININGS  
FOR  
TUNNELS,  
SEWERS,  
TANKS.


Specialists in the Repair and Reconditioning of  
Reinforced Concrete Structures, etc.

THE

Telegrams :  
Ganite  
Hitchin

**GUNITE**  
CONSTRUCTION CO LTD  
WESTERN HOUSE, HITCHIN, HERTS.

Telephone :  
Hitchin  
4371



OVER \*

the

Forth

\* UNDER

the Clyde


Colvilles Reinforcing Bars are being used extensively in the Forth Road Bridge project and in the approaches and portals of the new Ten million pound Clyde Tunnel. For hot-rolled, indented reinforcing bars specify 'COLBOND 60' which have a guaranteed minimum yield point of 60,000 lbs. per square inch.



**COLVILLES**

FITNESS FOR PURPOSE STEELS

COLVILLES LIMITED 195 West George St., Glasgow C.2.



For compacting mortar cubes  
for compression tests to  
B.S. 12/1958, 146, 1370, 915  
Automatic Time Control

# "CAPCO"

## H.F. VIBRATOR

"CAPCO" CONCRETE TESTING APPARATUS also includes:  
Cube Moulds; Slump Cones; Tensile, Vicat and Cylindrical  
Moulds; Compacting Factor Apparatus—Standard and Auto-  
matic; Sieve Vibrators and Sieves; etc.

### CAPLIN ENGINEERING CO. LTD

ALPAX WORKS, ST. LEONARDS ROAD, WILLESDEN JUNCTION, LONDON, N.W.10  
'Phone: ELGAR 7191. Grams: CAPLINKO, London, N.W.10. Cables: CAPLINKO, LONDON

WATERTIGHT  
LININGS  
FOR  
RESERVOIRS,  
SWIMMING  
POOLS, ETC.



LININGS  
FOR  
TUNNELS,  
SEWERS,  
TANKS.

*Specialists in the Repair and Reconditioning of  
Reinforced Concrete Structures, etc.*

THE

Telegrams :  
Gunito  
Hitchin

**GUNITE**  
CONSTRUCTION CO LTD  
WESTERN HOUSE, HITCHIN, HERTS.

Telephone :  
Hitchin  
4571

cubes

915

rol

D "

TD

s

s.


s.

s.

home

able

71



OVER \*

the

Forth

\* UNDER

the Clyde

Colvilles Reinforcing Bars are being used extensively in the Forth Road Bridge project and in the approaches and portals of the new Ten million pound Clyde Tunnel. For hot-rolled, indented reinforcing bars specify 'COLBOND 60' which have a guaranteed minimum yield point of 60,000 lbs. per square inch.



**COLVILLE'S**

FITNESS FOR PURPOSE STEELS

COLVILLE'S LIMITED 196 West George St., Glasgow C.2.



## TAKE A GOOD LOOK AT THE SURFACE

The water tower illustrated has a protective Stic B stone covering stipple finish similar to that shown in the smaller photograph. Treated in this way it is completely protected from the atmosphere and will require no further attention for many years. Stic B can

be applied direct to new or old concrete and most other building surfaces. No other material affords such lasting protection, while remaining so easy to apply.

Descriptive literature available.

# STIC B PAINT SALES LTD.

99 WANDSWORTH ROAD,

VAUXHALL, S.W.8

Telephone: RELiance 5566/2178 Telegrams: Sticbeelum, London, S.W.8

# Steel Reinforcement



A complete service of Design, Fabrication and Fixing of Steel Reinforcement for all types of Reinforced Concrete Construction.

M.S. Bars to B.S.S. 785, bent, bundled and labelled, delivered to site ready for fixing. No loss of time in checking and sorting material. No loss of material due to prolonged storage on site.

**T. G. JONES**  
AND COMPANY LIMITED



**REINFORCEMENT ENGINEERS**  
17 BUCKINGHAM PALACE GARDENS,  
LONDON, S.W.1 Tel: 8100ne 5271  
Head Office: Wood Lane, London, W.12  
Tel: Shepherds Bush 2628  
South Wales Office: Buts Street, Cardiff  
Tel: 28785  
Works: Shepherds Bush, London. Neath, Midx.  
Treorchy, Glam.

STORERS

W.M. T. STORER & Co. LTD.

TIMBER IMPORTERS AND MERCHANTS

*Established 1913*



*Sawing and Planing Mills:*  
RIVER ROAD, BARKING, ESSEX

Telephone: RIPPleway 0301 (10 lines)

FOR

WORKWOOD



BLUE CIRCLE RESEARCH  
AN AID  
TO  
BETTER BUILDING

Well aware of the need to keep ahead of the ever-changing requirements of the world's markets, the

Blue Circle research scientists are always seeking to improve existing products, to devise fresh uses for those products, and to develop new materials

to correspond with the development of new constructional techniques.

Take advantage of the benefits of this research—made possible only by the resources and experience of the largest cement organisation in the world.



THE CEMENT MARKETING CO. LTD. Portland House, Tethill St., London, S.W.1  
G. & T. EARLE LIMITED, Hull

THE SOUTH WALES PORTLAND CEMENT & LIME CO. LIMITED, Penarth, Glam.

# CONCRETE ROADS FIRST because CONCRETE ROADS LAST

REINFORCEMENT

by McCALLS

Glossop Road, Sheffield. City Engineer—R. Nicholas, C.B.E., M.I.C.E.  
Reinforced concrete slab, reinforced with "Matobar" fabric.

**McCALL & COMPANY (SHEFFIELD) LIMITED**

TEMPLEBOROUGH • SHEFFIELD • P.O. BOX 41

Telephone: ROTHERHAM 2076 (P.B. Ex. 8 lines)

LONDON: SLOANE 9428

PORTSMOUTH: COSHAM 78782

BIRMINGHAM: ACOCKS GREEN 6229

MC CALL & COMPANY (SHEFFIELD) LIMITED

MC CALLS MACALLOY LIMITED

PRECISION ROOFS LIMITED

MC CALLS MACALLOY AFRICA (PROPRIETARY) LIMITED

MC CALLS MACALLOY (AUSTRALIA) PTY. LIMITED

MC CALLS MACALLOY (CANADA) LIMITED

5RB96



# IBECO

WATERPROOF PAPER

## IN CONCRETE ROAD CONSTRUCTION

Recommended quantities for concrete work are IBECO No. 40 to B.S. 1521/1949 Class B and IBECO No. 60, the choice depending on the stresses involved. The former fully meets the specification at the lowest possible cost. As well as preventing seepage from the mix IBECO also checks the upward penetration of harmful acids and other chemicals frequently occurring in subsoils. It also has useful applications as a curing overlay. There is no free bitumen in IBECO to sweat out under exposure to hot sun. We will gladly send samples on request.

For the essential retention of water in a concrete mix to ensure sound setting and hardening, careful contractors are more and more depending on IBECO... Like no other waterproof paper, IBECO is waterproof *throughout its texture*. The proofing bitumen is part of the paper itself. Folding, creasing, even heavy trampling will not impair IBECO's impermeability... It's easy and quick to handle—speeds the work as well as lowering its cost and ensuring a better job. Remember IBECO for contracts in hand and in prospect.

### DAVIDSONS PAPER SALES LTD.

Head Office: Mugimoss Mills, Bucksburn, Aberdeen. Branches: 82/84 St. John Street, London, E.C.1. 31 North John Street, Liverpool 2. 9 Albion Street, Leeds. 42 Corporation Street, Newcastle-on-Tyne. Laird Place, Bridgeton Glasgow, S.E. Boroughmuir Square, Edinburgh. 4 Trinity Quay, Aberdeen.


**Testing  
concrete cubes  
on site**  
**MILBANK-WELLS**

**HYDRAULIC PRESS  
AND CUBE MOULDS**

Immediate Delivery

Two Sizes : 4 in. and 6 in.

PRESSES and CUBE MOULDS  
Testing to 16,000 lb. per sq. in. to  
B.S. 1081.



Approved for  
all Government  
Contracts

IN USE  
ALL OVER  
THE WORLD

6-IN. PRESS  
258 TONS

**£245**

4-IN. PRESS  
110 TONS


**£125**

**MILBANK FLOORS LTD**


**PRESTRESSED CONCRETE CONSTRUCTION**

**TYME HOUSE, EARLS COLNE, ESSEX**

Telephone: Earls Colne 410



**PRESTRESSED** FLOORS & ROOFS SPANS UP TO 40 ft.  
FRAME BUILDINGS ALL TYPES




THE MOST ADAPTABLE FRAME BUILDINGS  
FOR INDUSTRIAL AND AGRICULTURAL

**SINGLE SPAN • MULTI SPAN • CANTILEVER**

# Vibro

## CAST-IN-PLACE CONCRETE PILES



*This new church at Vlaardingen near Rotterdam is founded on fifty-nine 17-in. diameter Vibro piles 81 ft. long. The working load per pile is 68 tons, and 19-in. and 24-in. diameter shoes were used to develop the appropriate bearing capacity.*

The Vibro process ensures the formation of a pile consisting of dense, compressed concrete which has not been subjected to any driving stresses. The pile is adaptable in length, diameter and size of shoe to suit the ground conditions and carries its load with ample safety, yet without waste.

Vibro piles cannot be smaller than full size, need only light reinforcement and are formed rapidly and economically.

*For further details write for List No. 208*



TECHNICAL REPRESENTATIVES THROUGHOUT THE WORLD

**THE BRITISH STEEL PILING CO. LTD.**

10 HAYMARKET, LONDON, S.W.1.

Telephone: TRAfalgar 1024

BSP 179

## Proceedings of a Symposium on THE STRENGTH OF CONCRETE STRUCTURES

The proceedings of the Symposium on the Strength of Concrete Structures, organised by the Cement & Concrete Association in conjunction with the Joint Committee on Structural Concrete and held in London in 1956, are now available. The publication contains the complete text of seventeen papers, a general report on each of the five sessions, a report of the discussions on the papers, and the authors' replies. The principal subjects dealt with are:

**T**he theory of probability in the estimation of design loads.

**D**etermination of the factors for design.

**T**he specification of safety factors for structures.

**S**trength of members reinforced in tension only.

**S**trength of members in bending and torsion, and prestressed members.

**M**oment-distribution in continuous beams with plain and deformed bars.

**F**ailure of concrete under compound stress.

**S**trength of members under dynamic loads.

**U**ltimate-load design of reinforced and prestressed frames.

**S**tatically-indeterminate prestressed structures.

**P**restressed continuous beams and frames.

**W**alls subjected to axial and eccentric loads.

**S**imply-supported slab bridges subjected to concentrated loads.

**L**oad-factor methods according to British, Danish, and American practice.

OVER 600 PAGES

### ORDER FORM

To CONCRETE PUBLICATIONS, LTD., 14 DARTMOUTH STREET,  
LONDON, S.W.1, ENGLAND


Please send to the address below.....copy (copies) of the "Proceedings of a Symposium on the Strength of Concrete Structures." A remittance for ..... is enclosed.

BLOCK LETTERS  
PLEASE

NAME .....  
ADDRESS .....

\* Price by post, £5.

20 dollars in U.S.A. and Canada.



**200  
cycles  
INTERNAL VIBRATORS  
without flexible drives**

**ALLAM**

*Now fitted with overload and anti-single-phase switches.*


This new internal vibrator dispenses with the use of flexible drives. It has a frequency of 12,000 r.p.m. which, combined with amplitude, provides exceptional compaction of very harsh mixes. Vibrators of varying sizes, together with single- and multi-tool generators (Petrol, Diesel, and Electric drives), make this the most versatile range of internal vibrators so far available. It is in full production, and has already proved of considerable value to Contractors, Builders, and Precast Concrete Makers. Complete details of these and the range of Allam Vibrating Equipment will be sent on request.

**E·P·ALLAM & CO. LTD.**

**LONDON: 132-135 Sloane Street, S.W.1. • Telephone: Sloane 9976 (5 lines)**

Works: Southend-on-Sea Tel.: Eastwood 523243

**AGENTS & DISTRIBUTORS:** Strangford Ltd., Belfast and Dublin; A. Gunn & Co. Ltd., Altringham, Chas.; O. L. Davies Ltd., Port Talbot, Glam.; J. Lewis (Machinery) Ltd., Burslem, Stoke-on-Trent; G. B. Corner & Son, Leeds and Nottingham; John Resistone Ltd., Newcastle-on-Tyne; W. R. Salwood, Ltd., Chandler's Ford, Southampton; J. A. McAra & Co. Ltd., Glasgow.



P15 PORTASILO working on the construction  
of Wilmslow Grammar School, Cheshire.  
Contractors: L. Brown & Sons Ltd. Wilmslow

**FOR HANDLING CEMENT IN BULK**

- Fully proved on thousands of sites
- A range to suit all Concrete Mixers
- No condensation problems
- Backed by a first class after sales service
- Fully automatic, remote push button control provided by the addition of the Portasilo 'Autofeed' which can be interchanged between Portasilos as required
- FOR SALE OR HIRE

**PORTASILO LIMITED**

CONTRACTORS PLANT DIVISION, CORONATION ROAD, PARK ROYAL, LONDON N.W. 10  
Telephone: ELSAR 6214 - 6215 - 3726  
HEAD OFFICE: YORK  
AND AT BIRMINGHAM, MANCHESTER, GLASGOW, BRISTOL, BELFAST AND DUBLIN

Write or phone today for details of full range of 11, 15, 20 and 30 ton capacity models or ask for a representative to call



# CONCRETE AND CONSTRUCTIONAL ENGINEERING

INCLUDING PRESTRESSED CONCRETE

Volume LV, No. 3.

LONDON, MARCH, 1960.

## EDITORIAL NOTES

### "A Word is Wanted" : Report on the Competition.

THE misconceptions that can be caused by the use by technologists of wrong and misleading words are well shown in many of the suggestions entered in the competition, announced in this journal in September last, for a word to describe the material (generally steel wire or bars) used to put concrete into a state of compression and thereby produce what is known as prestressed concrete. The term prestressed concrete is itself unsatisfactory because it does not indicate the kind of stress to which the concrete is subjected. Worse was to come when the terms pre-tensioned concrete and post-tensioned concrete were coined to describe concrete which is in fact compressed; in both cases the prefixes indicate the time when the steel—not the concrete—is tensioned. There were more than fifty entrants for the competition and the number of different words submitted exceeded one hundred; some words were submitted by more than one entrant.

The comments in the following are based on the assessor's report of the competition, the purpose of which was to find an acceptable word that would describe the material used to put the concrete into a state of compression and that would indicate this function. Yet nearly a third of the words submitted implied that the prestressing material was stretching rather than compressing the concrete. Among these words are tensor, tenser, tent, tensioning element, tensingforce, tensilers, tensiles, and tensection. One competitor went so far as to suggest the word stretcher to describe the material that compresses the concrete. All these words using or based on the word tension indicate that the competitors who submitted them are the victims of the terms pre-tensioned concrete and post-tensioned concrete, and are in the habit of describing a prestressed member as being tensioned when in fact they well know that it is compressed. Words based on tension would be more aptly used to describe the jack or other means of tensioning the steel rather than the material which applies a compressive force to the concrete. This is an excellent example of the reason for the complaint so often heard that scientists and technologists have invented a language of their own which makes them unintelligible to the rest of the community. It also indicates that men with a knowledge of philology and semantics should be consulted before new technological terms are adopted, particularly when British Standards and codes of practice are being prepared. The unthinking generally

accept without question the terminology of a document having an official appearance, however wrong or foolish it may be.

Much nearer the mark were the competitors who submitted entries based on the word compression. Among such words were compression, precompression, compressus, compressing agent, compressifier, comprelement, pressinforcement, and presser, none of which, however, found favour with the assessor. In this group were pressure band (which suggests an element wrapped around the concrete) and pressing member (which indicates an external member applying a pressure to the concrete and which therefore would not be applicable when the force in the steel is transferred to the concrete by bond). Other entries indicating compression were clenchment for the material used to compress the concrete, clenching to describe the application of the prestressing force, and clenched concrete as an alternative to prestressed concrete. The act of clenching is, however, a local operation of closing tightly or grasping firmly, and is in no way similar to the compressing of a concrete member, particularly when the steel is pre-tensioned; there seems to be no analogy between effecting permanent compression and the clenching of teeth or fists—or nails.

Many entries were based on the word stress, including stresser and stressor, stress agent and stressing agent, stresscon, stressment, and—stress conditioner! All these words have the disadvantage that they do not indicate the kind of stress applied to the concrete.

Many competitors attempted to find a word similar to reinforcement, such as preforcement, preinforcement, forcement, and contraforcement, and another competitor suggested the use of preforced concrete in place of prestressed concrete. These words suffer from their similarity to reinforcement, with a consequent risk of confusion.

The assessor makes the following comments on some of the other entries. Bracement and embracement, and fortified (concrete) have well-known meanings, and it does not seem worth while to give them another meaning, and the same applies to lacing, latticing and webbing. Active reinforcement seems to have no meaning. Comprimer is a French verb meaning to compress, and its adoption in other countries as a noun describing a variety of materials in a state of tension does not seem advisable. Forceion carries its own condemnation. Strire is no doubt intended to describe a stretched wire; if this were adopted we should also need strod to describe a stretched rod and strope for a stretched wire rope. Sindon, suggested by the Greek verb meaning to bind together, is at first sight attractive, but in Latin the word sindon means fine linen or lawn. Sennon, sinnen, and sinnen are old spellings of the modern word sinew, and the use of one of these would seem to be a little far-fetched; besides, a sinew is a tissue uniting a muscle to a bone, and is in tension only when a force is applied to it by a muscle.

As stated in our February number the assessor awarded the prize of £25 to Mr. Paul L. Sowerby, of West Didsbury, Manchester, for the word strictor. This is based on the supine *strictum* of the Latin transitive verb *stringere*, meaning to draw or tie tightly, to press together, to tighten. The word strictor consists of the stem *strict-*, with the suffix *-or* converting it into an agent noun indicating a thing that acts. It seems that of all the suggestions received the word strictor best indicates imparting to a concrete member, by compression, a degree of rigidity which it would not otherwise possess.

## Slabs Spanning in Two Directions Designed by the Yield-line Method.

### UNIFORMLY-DISTRIBUTED LOADS.

By G. M. MILLS, B.Sc.Tech., A.M.I.C.E., A.M.I.Struct.E.

RECTANGULAR panels of slabs spanning in two directions may, according to British Standard Code of Practice No. 114, be designed by three methods, one of which requires the moment of resistance to be computed by the load-factor method and the determination of the strength by Johansen's yield-line theory.<sup>(1)</sup> This method may result in considerable saving of material and gives greater flexibility in design than alternative empirical methods. For example, the




Fig. 1.

moment of resistance over the supports may be arbitrarily equal to the moment of resistance at mid-span, thereby enabling freer use to be made of bent-up bars.

#### Pattern of Fractures.

For uniformly-distributed loads the pattern of the fractures which develop at failure are normally as in *Fig. 1a*. The provision of additional reinforcement in the top at the corners restricts the formation of the triangular area *Z*. Sufficient additional reinforcement eliminates this area, thus giving the pattern in *Fig. 1b*. Where the slab is continuous over an edge an additional fracture develops along the edge before complete failure occurs.

The principal notation as given in *Fig. 1b* is self-explanatory.

#### Formulae for Design.

There is an infinite number of combinations of reinforcement in the two orthogonal directions and at the supports of a slab which give the same strength. An economical arrangement may be obtained more readily by the use of various devices. Consider the slab in *Fig. 1b*. Assume that there are no shearing forces at the fractures and that the slab is homogeneously reinforced. If  $\mu = 1$ , Ingerslev showed that, for a uniformly-distributed load  $w$  per unit area,

$$M_x = \frac{wl_{yy}^2}{24} \left[ \sqrt{3 + \left( \frac{l_{yy}}{l_{xx}} \right)^2} - \frac{l_{yy}}{l_{yy}} \right]^2 \quad (1)$$

in which the reduced lengths of the sides  $l_{yy}$  and  $l_{xx}$  are

$$\frac{2l_y}{\sqrt{1 + i_2} + \sqrt{1 + i_4}} \quad \text{and} \quad \frac{2l_x}{\sqrt{1 + i_1} + \sqrt{1 + i_3}} \quad \text{respectively.}$$




Fig. 2.—Nomogram for Bending-Moment Coefficients (uncorrected).

If  $\mu$  is not equal to unity, Hognestad<sup>(1)</sup> shows that the slab may be analysed as an isotropically reinforced slab provided that the linear dimension parallel to the reinforcement giving the yield moment  $\mu M_s$  is divided by  $\sqrt{\mu}$  while the load  $w$  is unaltered. Substituting in equation (1),

$$M_s = \frac{wl_{sr}^2}{24} \left[ \sqrt{3 + \mu \left( \frac{l_{sr}}{l_{yr}} \right)^2} - \frac{l_{sr}}{l_{sr}} \sqrt{\mu} \right]^2 = \beta_s w l_{sr}^2.$$

The tabulation of values of  $\beta_s$  for different values of  $\mu$  and  $\frac{l_{yr}}{l_{sr}}$  are obtained from the nomogram in Fig. 2. Values for  $\beta_s$  and  $\beta_y$  are plotted against the ratio of the reduced spans  $l_{yr}/l_{sr}$  such that the yield-moment at mid-span of the shorter span is  $\beta_s w l_{sr}^2$  and of the larger span is  $\beta_y w l_{sr}^2 = \mu \beta_s w l_{sr}^2$ .

The positions of the fractures can be obtained from the same assumptions and are required for calculating the load carried by the supporting beams, which may differ considerably from the load allowed if the design is by the elastic method.

It can be shown that  $j$  is  $\frac{\sqrt{1+i_1}}{\sqrt{1+i_1} + \sqrt{1+i_3}}$ , and, if  $k' = \frac{k_1 + k_3}{2}$ , then  $\mu M_s = \frac{w(k' l_{yr})^2}{6}$ . Values for  $k'$  are also plotted on the nomogram (Fig. 2).

#### Correction for Corner Effects.

The coefficients obtained from the nomogram must be corrected to allow for the formation of additional fractures at the corners of the slab as shown in Fig. 1a. This effect reduces the strength of the slab, and the bending moments used in the design must be increased accordingly. Also  $k'$  may increase by an amount not exceeding 4 per cent. Let  $i_e M_s$  be the yield moment over the support at the corner of the transformed isotropically-reinforced slab. If the values of  $i$  for the two adjacent sides are equal and  $R_e = \frac{i_e + 1}{i + 1} = 1$ , Johansen shows that the correction for a square slab is 9.1 per cent. and that this is a maximum. Other percentages for a square slab are 6.8 for 1.1, 4.4 for 1.2, 1.8 for 1.3, and 0 for 2. If the transformed slab is not square, the correction for corner effects at a corner where the values of  $i$  for two adjacent sides are equal can be obtained from Fig. 3 in which the correcting factor is plotted against  $\frac{l_{yr}}{l_{sr} \sqrt{\mu}}$  for various values of  $R_e$ .

It is therefore usually economical to provide some additional reinforcement in the top of the slab at the corners where the corner yield-moment can be obtained without increasing the thickness of the slab, for example in the case of a freely-supported slab. When additional corner reinforcement is provided in one direction only, as at a corner with one adjacent side freely supported and the other continuous, the reduction in the corner effect depends on the angle between the line of the fracture and such additional reinforcement, but cannot be reduced to simple terms. The following empirical rule is suggested for the design of such corners.

Let  $iM_r$  be the support yield-moment at the continuous edge of a slab with a yield-moment of  $M_r$  at mid-span in a parallel direction and  $\mu M_r$  at mid-span

in a direction at right-angles. If reinforcement is provided in the top at the corners and parallel to the continuous edge to produce a yield-moment of  $i\mu M_r$ , then  $R_e = \frac{1+i}{1+vi}$  approximately, in which  $v = \frac{l_1}{l_1 + l_2\sqrt{\mu}}$  and  $l_1$  and  $l_2$  are the lengths of the continuous and the freely-supported edges respectively. One-quarter of the correction factor for each such corner should then be obtained from *Fig. 3*.

### Economical Amount of Reinforcement.

The condition that  $i_1 = i_2 = i_3 = i_4$  is generally convenient for a fully-continuous slab. If, also, the area of reinforcement in each orthogonal direction is proportional to the corresponding design moment at mid-span, the total weight of reinforcement is proportional to  $M_s + \mu M_s = S$  such that

$$S = (1 + \mu) \left[ \sqrt{3 + \left( \frac{l_{sr}}{l_{yr}} \right)^2 \mu} - \frac{l_{sr}}{l_{yr}} \sqrt{\mu} \right]^2 C' \frac{\pi l_{sr}^2}{24},$$

in which  $C' = 1 +$  (correction factor for corner effects). The correction factor is a function of  $\mu$ , but it is reasonable to consider  $C'$  as relatively constant. To find

the minimum weight of reinforcement, from  $\frac{dS}{d\mu} = 0$ ,  $\mu = \frac{\left( \frac{l_{sr}}{l_{yr}} \right)^2}{3 - 2 \left( \frac{l_{sr}}{l_{yr}} \right)^2}$ . It will be

found that the lines on the nomogram giving the values in *Table I* all pass through unity on line F. Similarly it can be shown that if  $\mu \times$  (weight of reinforcement in the  $M_s$  direction)  $\div$  (weight of reinforcement in the  $\mu M_s$  direction)  $= F$ , then

TABLE I.

$\frac{l_{yr}}{l_{sr}}$	1	1.1	1.2	1.3	1.4	1.5	1.75	2
$\mu$	1.000	0.610	0.430	0.325	0.260	0.210	0.140	0.100
$\beta_x$	0.042	0.056	0.067	0.076	0.083	0.088	0.098	0.103
$\beta_y$	0.042	0.035	0.029	0.025	0.022	0.019	0.014	0.011

the most economical distribution of reinforcement occurs when the lines on the nomogram cut line F at the corresponding ratio. It is assumed in the foregoing that the area of reinforcement is proportional to the yield-moment. This is not correct, but the error is negligible.

### Position of Reinforcement.

The reinforcement should be designed so that the elastic moments developed are approximately proportional to the design yield-moments. This method not only prevents yielding of reinforcement at working loads but also reduces the widths of the cracks on the face of the slab in tension. For the same reason it may be advisable to adopt a minimum value for the coefficient for the bending moment on the longer span.

Reinforcement to give the design moment of resistance must be provided across all normal lines of fracture. Reference to *Figs. 1a* and *1b* indicates the critical sections which must be reinforced.




Fig. 3.—Correction for Corner Effects.

Sufficient reinforcement must be provided at other positions to prevent fractures developing across what would otherwise be weakly-reinforced sections and so lead to the collapse of the slab at a load less than the ultimate design load. For example, if reinforcement is omitted from the bottom of the edge strips parallel to the sides in the manner recommended in B.S. Code No. 114, Clause 314b (ii), a possible pattern of fractures is shown in *Fig. 4a* and may result in a lower strength than a homogeneously reinforced slab.

*Table II* gives typical results obtained by analysis of slabs continuous on four sides in which the moment at the support is equal to the parallel mid-span moment of resistance. The distribution of the reinforcement is "economical".

TABLE II.—VALUES OF  $\frac{M_{d,2}^2}{M_x}$

$\frac{l_y}{l_x}$	Homogeneous	Edge strip $\frac{l_x}{12}$ wide	Edge strip $\frac{l_x}{6}$ wide	
			Corner panel $\frac{l_y}{4} \times \frac{l_x}{4}$	Corner panel $\frac{l_y}{3} \times \frac{l_x}{3}$
1.0	44.0	43.8	39.9	46.3
1.2	27.7	27.3		
1.4	22.6	22.3	20.8	23.5
1.6	20.3	20.0		

Fracture pattern as in *Fig. 4a*.

The determination of the positions at which bars comprising the reinforcement over the supports may end also depends on the need to avoid the development of a pattern of fractures resulting in reduced strength. Consider the slab in *Fig. 4b* which is continuous along one side only. Assume that a fracture develops in the top face a distance  $nl_x$  from the continuous edge where there is no reinforcement in the top.

If the strength in this condition is the same as when the fracture occurs along the support, then  $l_{sr} = l_s - nl_s$ . The length of the reinforcement over the support is therefore dependent on the ratio  $i$ . With continuity over two opposite edges, a similar equation determines the minimum value for  $n$ . Values of  $n$  are given in




Fig. 4.

Table III which applies only to homogeneously reinforced slabs. If reinforcement is omitted from the bottom in the edge strips, a correction must be applied. It is essential to continue the bars a short distance beyond these points to provide for bond.

TABLE III.—MINIMUM VALUES OF  $n$ .

Value of $i$	1	1½	2½	3
Continuous over one side	0.18	0.20	0.23	0.27
Continuous over two opposite sides	0.15	0.17	0.19	0.22

Similarly, the positions at which a proportion of the reinforcement in the top may be bent down into the bottom of the slab can be determined. For example, reinforcement corresponding to  $0.5 M_x$  may be bent down at  $n = 0.1$  for any value of  $i$  if  $M_x$  is the corresponding moment of resistance at mid-span.

Summarising the foregoing, reinforcement may be omitted from the bottom of the edge strips of width  $l_s/12$  and parallel to the adjacent side subject to the provision of distribution bars and reinforcement in corner panels on sides equal to  $l_s/4$ . If such a system is adopted the design moments must be increased by 2 per cent. (see Table II) and the length of reinforcement over the support by  $(0.02 \times \text{span})$ .

As fractures along continuous supports will occur at the face of the supporting beams, the effective span may be assumed to be the distance between the faces of the beams, and by so doing the design moments may be reduced by as much as 10 per cent. If a slab is not continuous over a support but is constructed monolithically with the support, the ultimate restraining moment afforded by such a connection can be calculated and this may be taken into account in determining the greatest load that can be carried by the slab.

#### Example.

A panel of slab 16 ft. by 24 ft. which is continuous over one longer side and freely-supported along the other three sides is to carry 120 lb. per square foot in addition to its weight. In this case the ratio of the elastic moment at the support

to that at mid-span (using Dr. Marcus's method as modified by Professor B. Loser) depends on whether the panel is one of a row or one of two panels and would be either 1.6 or 1.9 respectively. Therefore  $i$  is preferably between 1.5 and 2.0.

$$\text{If } i = 1.5, l_{sr} = \frac{2 \times 16}{1 + \sqrt{2.5}} = 12.44 \text{ ft., and } \frac{l_{yy}}{l_{sr}} = 1.93.$$

Assume that the area in plan of the reinforcement at the support is  $0.25 \times (\text{area of reinforcement at mid-span})$ , then  $F = 1 + (0.25 \times 1.5) = 1.37$ .

CONCRETE		A	B	Loading. Imposed 120 lb. per sq. ft.					
1:2:4 (1000 lb. per sq. in.)		16' 0"	16' 0"	5' slab	63	= = =			
SHORTER SPAN		$i$	$F$	$l_{sr}$	$\frac{l_{yy}}{l_{sr}}$	CORRECTION	$\beta_x$	$\beta_y$	
		1.5	$1 + \frac{1.5}{4}$ $= 1.37$	$\frac{2 \times 16}{1 + \sqrt{2.5}}$ $= 12.44 \text{ ft.}$	$\frac{24}{12.44} = 1.93$	Edge strips: 2% Corners (say) 2%	0.095	0.23	
				$M_x = 0.095 \times 1.04 \times 183 \times 12.4^2 = 2780 \text{ ft-lb.}$ Bardia $\frac{4}{8}$ , Cover $\frac{5}{8}$ , $d_1 = 4.06$ . $M_r = \frac{260 \times 4.06^2}{12} = 4120 \text{ ft-lb.}$ $M = \frac{2780}{4.06^2} = 168$ ; Reinf. = 0.97%; $A_{st} = \frac{0.97 \times 12 \times 4.06}{100} = 0.47 \text{ sq. in.}$					
				REINFORCEMENT		% (ACTUAL)	$M_r$ (actual)		
		Bottom: $\frac{5}{8}$ at 8" c/c.		0.95		163	$= 16 \times 4.06^2$		
		Top: $\frac{5}{8}$ at 8" c/c.		1.57		240	$= 2680 \text{ ft-lb.}$		
		A-D $\frac{5}{8}$ at 8" c/c.							
		Corner Panels $\frac{1}{2}$ at 12" c/c.		0.80		76	$i_{\text{actual}} = \frac{240}{163} = 1.47$		
		Top C & D							
LONGER SPAN		$l_{sr}$	$\frac{l_{yy}}{l_{sr}}$	CORRECTION		$\beta_x$ ACTUAL	$\beta_y$		
		$\frac{2 \times 16}{1 + \sqrt{2.5}}$ $= 12.44$	24 $= 1.93$	$C-D$ $\frac{l_{yy}}{l_{sr}} = \frac{1.93}{12.44} = 1.53$	$\frac{1.53}{4.06^2} = 4$ If 50% $M_r$ , correction = 0.	$\frac{2.68}{183 \times 1.03 \times 12.44^2}$ $= 0.092$			
				A-D Provide 1.47 My					
				$M_r = \frac{1.47 \times 12.44^2}{1 + 0.76 \times 1.47} = 1.16$					
				Correction = $2 - \frac{1}{2} = 1\frac{1}{2} = 1\frac{1}{2}$					
				$M_y = 0.092 \times 1.03 \times 183 \times 12.4^2 = 700 \text{ ft-lb.}$					
				Bardia $\frac{5}{8}$ , Cover = $1\frac{1}{2}$ , $d_1 = 3.56$ .					
				$M = \frac{700}{3.56^2} = 55$ ; Reinf. = $0.76 \times 1.47 \times \frac{0.24}{100} \times 12 \times 3.56 = 0.124 \text{ sq. in.}$					
				Bottom: $\frac{5}{8}$ at 10" c/c.					
		Corner Panels: Top C & D: $\frac{5}{8}$ at 6" c/c.		Plot 1 lb. bars in top A-D: $\frac{5}{8}$ at 12" c/c.					

Fig. 5.

From the nomogram in *Fig. 2*,  $\beta_x = 0.095$  and  $\beta_y = 0.022$  before correction, giving  $\mu = 0.23$  and  $\frac{l_{yy}}{l_{xy}\sqrt{\mu}} = 4$ . From *Fig. 3*, for the correction to be zero,  $R_c$  must be about 1.4. This value can be obtained at the two corners with both edges freely supported if reinforcement is provided in the top to provide, say, in each direction, half the corresponding moment at mid-span. If the empirical method is adopted for the other two corners and  $1.5 \times$  (area of the parallel mid-span reinforcement) is provided at right-angles to the reinforcement in the top over the support,

$$R_c = \frac{1 + 1.5}{1 + 1.5v} \text{ in which } v = \frac{24}{24 + 16\sqrt{0.23}} = 0.76;$$

Therefore  $R_c = 1.17$  and the correction is  $2 \times \frac{1}{4} \times 2$  per cent. = 1 per cent. Therefore  $M_x = 0.096 \times 12.44^2 \times w$  ft.-lb. With a 5-in. slab the total load is  $120 + 63 = 183$  lb. per square foot, and  $M_x$  is about 2700 ft.-lb.

If  $i = 2.0$ ,  $l_{xy} = \frac{2 \times 16}{i + \sqrt{3}} = 12.1$  ft., and  $\frac{l_{yy}}{l_{xy}} = 1.98$ . The area over which

the reinforcement at the support must be provided is increased to, say,  $0.3 \times$  (area of mid-span reinforcement) as shown in *Table III*. Therefore

$$F = 1 + (0.30 \times 2) = 1.6.$$

Proceeding as before,  $\beta_x = 0.092$  and  $\beta_y = 0.027$  before correction, and the correction is again found to be 1 per cent. Therefore

$$M_x = 0.093 \times 12.1^2 \times 183 = 2500 \text{ ft.-lb.},$$

and the moment at the support is 5000 ft.-lb. If the permissible compressive stress in the concrete is 1000 lb. per square inch, the moment of resistance, calculated by the load-factor method, of a 5-in. slab with  $\frac{1}{4}$ -in. bars and  $\frac{1}{2}$ -in. cover of concrete is only 4120 ft.-lb. By reducing  $\beta_x$  to 0.078 and increasing  $\beta_y$  to 0.053,  $M_x = 2060$  ft.-lb. and the moment at the support is 4120 ft.-lb. A comparison of the foregoing results with the bending moments (in ft.-lb. per foot width) calculated by use of the coefficients in *Table 17* of B.S. Code No. 114 is as follows.

Bending moment	Load-factor Method		Elastic Theory. Coefficients from Code No. 114 $i_x = 16.5$ ft.
	$i = 1.5$	$i = 2.0$	
Support: $iM_x$	4000	4120	4150
Midspan of $i_x$ : $M_x$	2670	2060	3110
Midspan of $i_y$ : $M_y = \mu M_x$	620	1350	2150

The first trial, that is with  $i = 1.5$ , gives the most economical design and the saving in reinforcement in a 5-in. slab compared with the elastic method is about 20 per cent.

The foregoing calculation shows the use of the nomogram and the graph for finding the correction factor; in practice, it may be more convenient to base the calculations on a selected arrangement of the reinforcement across the shorter span. A typical calculation sheet is shown in *Fig. 5* in which moments of resistance are obtained from load-factor tables.<sup>(2)</sup> For the short span a preliminary calculation

is carried out to determine the approximate "economical" moment of resistance as a guide to selecting suitable reinforcement. Using the value of  $i$  obtained thus, the reinforcement across the longer span is obtained by means of a more accurate calculation.

(1).—E. HOGNESTAD, "Yield-line Theory for the Ultimate Flexural Strength of Reinforced Concrete Slabs", *Journal of Am. Concrete Inst.*, March 1953.

(2).—J. S. COHEN, "Tables for the Design of Beams and Slabs", *Concrete Publications Ltd.*

### Residential Flats 97 ft. and 106 ft. High.

THE residential flats illustrated below, which have been erected at Shoot-up Hill for the Willesden Borough Council, comprise two structures 97 ft. high each of eleven stories and one structure 106 ft. high of twelve stories. The plan of each block is in the form of two rectangles one of which is about 63 ft. by 28 ft. and the other about 45 ft. by 35 ft. The two parts are connected by a structure containing the lift, about 22 ft. by 8 ft. The main roof is surmounted by tank-rooms, the lift-motor room, and a penthouse.

The structures have strip footings, and the floors, roofs, stairs, walls enclosing the stairs, and the lift shafts, some external walls, and the internal cross-walls are of reinforced concrete. The external concrete walls are faced with

brick or faience. The remaining external walls are of brickwork with an inner lining of clinker-concrete slabs. The internal partitions are also of clinker-concrete slabs. The beams, staircases, and balconies were precast.

The internal and external reinforced concrete walls, which were cast in place, carry the weight of, and loads on, the building to the foundation. The outer faces of the external walls were coated with a waterproofing bituminous compound before building the brick facing. There are also some single-story buildings.

The cost of the work is about £400,000. The architects are Messrs. Emberton, Franck & Tardrew. The designers of the reinforced concrete work and the contractors were Messrs. Wates, Ltd.



## Book Reviews.

**"Proceedings of a Symposium on the Strength of Concrete Structures."** Obtainable from Concrete Publications, Ltd. Price by post £5; in U.S.A. and Canada, 20 dollars.

THE proceedings of the Symposium on the Strength of Concrete Structures, organised by the Cement and Concrete Association and held in London in May, 1956, have now been published in a volume containing the seventeen papers, a general report and a record of the discussions. The subjects and authors of the papers are:

"Some Results of the Theory of Probability in the Estimation of Design Loads", by M. R. Horne. "Determination of the Design Factor for Reinforced Concrete Structures", by A. I. Johnson. "Current Trends in the Specification of Structural Safety", by Professor Sir Alfred G. Pugsley, O.B.E.

"Strength of Singly-reinforced Beams in Bending", by A. H. Mattock. "Strength of Concrete Members in Combined Bending and Torsion", by S. Armstrong. "Strength of Prestressed Concrete Members", by Professor C. P. Siess. "Moment Redistribution in Continuous Beams Reinforced with Plain and Deformed Bars", by K. Hajnal-Kónyi and H. E. Lewis. "Failure of Concrete under Compound Stress", by A. J. Harris.

"Ultimate-load Design of Reinforced and Prestressed Concrete Frames", by Professor A. L. L. Baker. "Strength of Statically-Indeterminate Prestressed Concrete Structures", by Y. Guyon. "Strength of Prestressed Concrete Continuous Beams and Simple Plain Frames", by P. B. Morice and H. E. Lewis.

"Strength of Concrete Walls under Axial and Eccentric Loads", by A. E. Seddon. "Strength of Concrete Members under Dynamic Loading", by S. C. C. Bate. "Strength of Simply Supported Slab Bridges subjected to Concentrated Loads", by P. B. Morice and G. C. Reynolds.

"Ultimate Strength of Reinforced Concrete in American Design Practice", by E. Hognestad. "Design of Reinforced Concrete Members", by A. Aas-Jakobsen. "Load-factor Design in Building Regulations: Future British Practice", by D. D. Matthews.

**"Examples of the Design of Reinforced Concrete Buildings in accordance with the British Standard Codes."** By Charles E. Reynolds. (London: Concrete Publications, Ltd. 2nd edition. 1959. Price 12s. 6d.)

NEW features in the revised British Standard Code No. 114 (1957), "The Structural Use of Normal Reinforced Concrete in Buildings", include the load-factor method of design of slabs, beams, and columns subjected to bending, and the analysis of flat slabs as parts of a frame. These matters and other unaltered or revised recommendations of the B.S. codes relating to the design of reinforced concrete buildings are dealt with in the second edition of this book, which has been almost completely rewritten and includes the revised notation. As in the previous edition the book is in two parts.

In the first part design data are considered in the same sequence as in design calculations, namely, loads, bending moments and shearing forces, stresses, resistance to bending and shearing, and bond. The structural parts of a building are then dealt with in the order in which design proceeds, namely, slabs, beams, columns and load-bearing walls, stairs, basements, and foundations. The method of moment-distribution applied to continuous beams and the design of hollow-block slabs and precast floors are included as in the previous edition, and among the new matter there is a consideration of concentrated loads on slabs spanning in one or two directions. More than sixty tables and numerous diagrams are provided to aid quick design.

In the second part the complete design of a typical multiple-story building is given in the form of calculations and drawings showing the arrangement of the members and the reinforcement. Alternative designs of beam-and-slab and flat-slab floors are given. Slabs spanning in two directions with and without the corners held down, cantilevered slabs, columns (with and without the effects of wind being taken into account), and the effect of bending in two planes are considered. The building is planned to incorporate as many of the recommendations of the British Standard Codes as is practicable.

## Prestressed Road Bridge of 110-ft. Span.

THE road bridge (Fig. 1) erected recently over the railway between Bickley and St. Mary Cray, Kent, has a span of 110 ft. and is one of the largest freely-supported prestressed concrete bridges of its kind in Britain. The deck (Figs. 3 and 4) comprises twelve longitudinal prestressed beams of tee-section on the top flange of which there is a layer of plain concrete and 2 in. of hot-rolled asphalt. Vertical slabs are provided at 12 ft. centres between the flanges. The overall width of the bridge, which is on a slight skew in relation to the railway, is 47 ft. 7 in.; the carriageway is 33 ft. wide and there is a 5-ft. footpath at each side with provision for pipes and

constructed first and road traffic was diverted to this part while the old structure was demolished (Fig. 2). The second part of the new bridge, comprising seven beams, was then constructed.

### Beams.

The beams were first designed to be precast at the site in one length of about 113 ft., but owing to the restricted space they were each precast in five parts at a factory. The three longer intermediate parts are each 25 ft. long. The vertical slabs between the flanges are 9 in. thick and are monolithic with the beams. The



Fig. 1.

services below. The parapets are steel hand-rails. Tubular guard-rails are provided between the footpaths and the carriageway.

Each beam is supported on concrete hinges (Fig. 5). At one end there is a simple hinge, and at the other end a rocker-type hinge. Each abutment is a continuous pile-cap 10 ft. wide supported on twenty-two cast-in-place piles, 14 in. in diameter and 30 ft. long, bored in the sides of the cutting.

The bridge, which is designed to carry the ordinary load specified by the Ministry of Transport and Civil Aviation, replaces a brick structure of three arches. A part of the bridge comprising five beams was

width of the beams (including the vertical slabs) as cast is such that there were gaps of 5 in. between adjacent beams, which were filled with high-alumina cement concrete. Before it was erected each beam was prestressed with eleven cables each containing twelve 0.276-in. wires which were tensioned one at a time. The anchor-plates at the end of a beam are shown in Fig. 7. The deck was prestressed transversely, as shown in Fig. 4. The concrete in the beams had a water-cement ratio of 0.40 and a crushing strength of not less than 7250 lb. per square inch at 28 days. The strength at seven days or at the time of prestressing was not less than 5000 lb. per square inch.

PRESTRESSED ROAD BRIDGE OF 110-FT. SPAN.

CONCRETE



Fig. 2.—The Old Bridge during Demolition.




Fig. 3.

**Hinges.**

The hinges (Fig. 5) are of the Freyssinet type as described by M. Y. Guyon in a paper entitled "Long-span Prestressed Concrete Bridges Constructed by the Freyssinet System" (Proceedings of the Institution of Civil Engineers, May, 1957). Double throatings are provided in the rocker hinges and a single throating in the fixed hinges. The hinges, which are lightly reinforced, are of high-alumina cement concrete cast in place. The beam bears directly on the top of the hinge from which a stub projects and registers with a recess in an iron ring 1½ in. diameter and 1 in. deep built into the soffit of the beam.

**Erection.**

The erection of the beams was hampered by the restricted working space on a busy road which had to be kept open for traffic, and the few hours each week during which it was permissible to work over the tracks. Each part of a beam was brought to the site on a lorry which backed under a steel gantry (Fig. 8) at the side of the road at one end of the bridge. The beam was lifted by two 7-ton lifting gears suspended from the gantry, and after the lorry had moved away it was lowered on to a bogie on a rail track and transported to the assembly bay (Fig. 9). Here the parts were arranged to form complete beams and supported on stools. Each stool comprised a concrete block surmounted by two steel beams. Steel packings were used to obtain the correct height; this was important, because it was necessary for the 2-in. ducts for the three transverse prestressing cables in each vertical slab to register exactly. It was also necessary to align the parts longitudinally to within  $\frac{1}{8}$  in. to ensure that the ducts (which are at 2 ft. centres) in the top flange were in alignment with the ducts in adjacent beams.

The four joints between the five parts comprising a beam are about 1 in. wide and were packed with dry mortar. Short lengths of inflatable rubber tube were inserted across the joints in the ducts for the longitudinal cables to prevent mortar gaining access to the ducts. Four days after making the joints, when the strength of the mortar was about 5000 lb. per square inch, the beams were prestressed, an operation occupying about two days. The hogging due to the prestressing raised




Fig. 4.—Half Cross Section AA (see Fig. 3) of Deck.




Fig. 5.—Details of Abutments.



Fig. 6.—Placing Beam in Position.

the beam off the stools, the steel bearings of which could then be removed and so permit bogies to be placed under the beam.

When it was possible to work over the tracks the beam was drawn on to the bridge by a winch. A steel gantry of span sufficient to cover the first five beams to be erected had been installed at each end of the bridge, as is seen in *Fig. 6*. Steel slings (*Fig. 10*) suspended from the gantries were placed around each end of the beam, and the beam, which weighs about 50 tons, was lifted off the bogies, moved laterally, and lowered into position. The concrete was then placed in the gap between the beam and the beam placed previously.

When the first five beams had been placed and the intervening gaps filled, cables were inserted in the ducts in the

flanges and the vertical slabs and tensioned, thereby prestressing transversely the first part of the bridge.

The road surface on this part was then laid and traffic diverted from the old bridge. The steel gantries were dismantled and, after demolition of the old bridge, were re-erected for erecting the remaining seven beams. When the first two of these beams had been laid, temporary transverse prestressing was carried out to tie these beams to the first part so that they could be used as a platform on to which the remaining beams could be drawn from the assembly bay. This procedure enabled the entire width of the



Fig. 7.

March, 1960.



Fig. 8.

first part to be used by traffic. The transverse prestressing was continued by attaching, by means of a double-ended joint, an additional length of cable to that already tensioned.

Because of the position of the inclined struts of the gantries, the outer beam could not be lowered into its final position directly. Therefore after the tenth beam had been placed, the outer (or twelfth) beam was lowered into the position of the eleventh beam and then moved laterally to its correct position. The eleventh beam was then placed in the space between the outer and tenth beams. The gaps were filled and the transverse prestressing continued across the entire width of the bridge.

The bridge was designed by the late Mr. J. A. Riccomini, Bridge Engineer, Roads




Fig. 9.

#### Non-destructive Method of Testing the Strength of Lightweight Concrete.

In the course of a paper presented to the American Society for Testing Materials in June, 1959, Mr. I. A. Benjamin and Mr. G. D. Ratcliff describe the results of an investigation on the use of a Proctor needle to ascertain the strength of concrete with a density of less than 40 lb. per cubic foot.

The procedure is to apply a Proctor needle to the concrete at any time more than six hours after it has been cast and to record the force required to cause the needle to penetrate to a depth of  $\frac{1}{2}$  in. Crushing tests of 2-in. cubes made of the



Fig. 10.

Department, Kent County Council, and was erected under the supervision of Mr. E. W. H. Vallis, at that time County Surveyor. This article has been prepared with the co-operation of the present County Surveyor, Mr. H. Bowdler, M.I.C.E. The contractors were Messrs. John Cochrane & Sons, Ltd., to whom Messrs. Bernard Clarke & Partners acted as consulting engineers. The precast blocks were made by Concrete, Ltd. The beams were prestressed by the Gifford-Udall system. The piles were supplied by the Cementation Co., Ltd.

same concrete showed that there was a consistent relation between the force applied to the needle and the compressive strength of the cubes at ages up to more than 21 days. Full details of the investigation are available from the Society (1916 Race Street, Philadelphia, Pa., U.S.A.) in the form of a preprint of a paper to be published later in the Bulletin of the Society.

#### A Low-cost Warehouse.

MR. S. STOHERT, who was associated with the design of the new warehouse described on page 40 of our number for January, 1960, is the staff architect of the Clayton Aniline Co., Ltd.

## Comparison of Analyses of Helical Stairs.

By V. A. MORGAN, M.Eng., A.M.I.C.E.

A HELICAL flight of stairs (*Fig. 1*) rises 11 ft. between the basement and ground floors of a new office building at Ealing, Middlesex, and has twenty-two 6-in. risers. A landing is provided 3 ft. 6 in. above the basement floor because the fire regulations do not permit a flight of more than fifteen steps. Above the landing the waist of the stairway is 8 in. thick but below the landing the waist is thicker to maintain an unbroken soffit. The flight turns through 360 deg. The imposed load was assumed to be 100 lb. per square foot of area in plan. Two methods were used for analysis. In one method it was assumed that the structure was freely supported, and in the other it was assumed to be fixed at the ends. The methods are described and compared in the following.

### Analysis of a Freely-supported Flight.

The notation used and a diagram of the stairs are shown in *Fig. 2*. Assuming that there are no vertical bending moments at the ends of the flight, the basis of the analysis is the formulae given by Mr. A. H. Mattock<sup>(1)</sup> which have been adjusted so that the origin is at C midway along the flight. From this point the angle  $\theta$  measured in a clockwise direction is positive and is negative in an anti-clockwise direction.



Fig. 1.

The angle of rise  $\phi$  is constant and  $\tan \phi = \frac{h}{R_2 \beta}$ , in which  $h$  is the effective height of the stair and  $\beta$  is the effective angle through which it turns;  $\gamma$  is 30 deg. In the following formulae  $\alpha = \theta - \gamma$  and  $\delta = \theta + \beta/2$ . At any point O in the flight,

$$\text{Vertical moment: } M_{ro} = wR_1 R_2 \frac{\beta}{2} \sin \alpha + wR_1^2 (1 + \cos \alpha) - \frac{Hh}{\beta} \delta \sin \theta . \quad (1)$$

Lateral moment:

$$M_{so} = \left[ wR_1 R_2 (\cos \alpha - \theta) - \frac{Hh}{\beta} \delta \cos \theta - wR_1^2 \sin \alpha \right] \sin \phi - HR_2 \sin \theta \cos \phi . \quad (2)$$

Torsion:

$$T_s = \left[ wR_1 R_2 (\cos \alpha - \theta) - \frac{Hh}{\beta} \delta \cos \theta - wR_1^2 \sin \alpha \right] \cos \phi + HR_2 \sin \theta \sin \phi . \quad (3)$$

$$\text{Thrust normal to the tangent: } P_{no} = -H \sin \theta \cos \phi - wR_1 \theta \sin \phi . \quad (4)$$

Shearing force across the waist of the stairs:

$$S_{no} = wR_1 \theta \cos \phi - H \sin \theta \sin \phi . \quad (5)$$

$$\text{Radial horizontal shearing force: } S_{hs} = H \cos \theta . \quad (6)$$

The vertical reactions at the supports are  $\frac{w}{2} R_2 \beta$ . Also  $\bar{x} = \frac{2R_1 \sin \frac{\beta}{2}}{\beta}$  and  $x = R_2 \sin \left( \frac{\beta}{2} - 90 \text{ deg.} \right)$ . Then  $Hh = W(\bar{x} + x)$  and  $M_{hs} = HR_2 \sin \gamma$ .

The values for these stairs are as follows.  $\beta = 300 \text{ deg.}$  The internal radius is 3 ft. and the width 4 ft. Therefore  $R_2 = 5 \text{ ft.}$  and the centre-line of the loads is  $\frac{2(7^{\frac{2}{3}} - 3^{\frac{2}{3}})}{3(7^{\frac{2}{3}} - 3^{\frac{2}{3}})} = 5.26 \text{ ft.} = R_1$  from the axis of the helix. The effective height  $h$  is the actual height minus one riser and is 10 ft. 6 in. The reactions occurring at the ends of the flight are 13,800 lb.,  $H = 14,040 \text{ lb.}$ , and  $M_{hs} = 35,100 \text{ ft.-lb.}$  Substituting these values in equations (1) to (6) the principal moments, forces, shears, and torque can be calculated and are shown by the full lines in Fig. 3.




Fig. 2.




Fig. 3.

## Analysis of a Flight with Fixed Ends.

The theory of strain-energy is applied, and the notation is shown in *Fig. 4*. The origin is point C and bending moments to the right of C are considered to be positive when acting in an anti-clockwise direction when viewed along their axes towards point O. To the left of C all signs are reversed. If  $M_r$  is the bending moment acting in a tangential plane at C, then

$$M_{rf} = M_r \cos \theta + HR_2 \theta \sin \theta \tan \phi - wR_1^2(1 - \cos \theta). \quad (7)$$

$$M_{nf} = (M_r \sin \theta - HR_2 \theta \cos \theta \tan \phi + wR_1^2 \sin \theta - wR_1 R_2 \theta) \sin \phi - HR_2 \sin \theta \cos \phi. \quad (8)$$

$$T_f = (M_r \sin \theta - HR_2 \theta \cos \theta \tan \phi + wR_1^2 \sin \theta - wR_1 R_2 \theta) \cos \phi + HR_2 \sin \theta \sin \phi. \quad (9)$$

and the following strain-energy equations may be applied:

$$\frac{\delta U}{\delta m} = 0 = \int_0^{\frac{\pi}{2}} \left( \frac{\delta M_{rf}}{\delta M} \cdot \frac{M_{rf}}{EI_1} + \frac{\delta M_{nf}}{\delta M} \cdot \frac{M_{nf}}{EI_2} + \frac{\delta T_f}{\delta M} \cdot \frac{T_f}{CJ} \right) R_2 d\theta. \quad (10)$$

$$\frac{\delta U}{\delta H} = 0 = \int_0^{\frac{\pi}{2}} \left( \frac{\delta M_{rf}}{\delta H} \cdot \frac{M_{rf}}{EI_1} + \frac{\delta M_{nf}}{\delta H} \cdot \frac{M_{nf}}{EI_2} + \frac{\delta T_f}{\delta H} \cdot \frac{T_f}{CJ} \right) R_2 d\theta. \quad (11)$$

in which  $C$  is the coefficient of rigidity =  $1.2 \times 10^6$  lb. per square inch,  $E$  is the elastic modulus =  $3 \times 10^8$  lb. per square inch,  $I_1$  and  $I_2$  are the moments of inertia of one step about a horizontal axis and vertical axis ( $\frac{bd^3}{12}$ ) and ( $\frac{db^3}{12}$ ) respectively,  $J$  is the polar moment of inertia ( $K_2 b^3 d$ ), and  $K_2$  as given by Timoshenko<sup>(2)</sup> is 0.31 when  $\frac{d}{b} = 6$ . Therefore  $\frac{CJ}{EI_1} = 1.49$  and  $\frac{CJ}{EI_2} = 0.0415$ .




Fig. 4.




Fig. 5.—Shuttering for Soffit and Edges.

From equations (10) and (11)

$$\frac{CJ}{EI_1}[(m+0.5 \sin 2\theta)(M_v + wR_1^2) - wR_1^2 \sin \theta - KHR_2 \tan \phi] + s[m(M_v + wR_1^2) + nwR_1R_2 + KHR_2 \tan \phi] + HR_2 \sin \phi \cos \phi m \left( 1 - \frac{CJ}{EI_1} \right) = 0 \quad . \quad (12)$$

$$\begin{aligned}
 & \frac{CJ}{EI_1} \left[ mwR_1^2 - K(M_v + wR_1^2) + \frac{HR_2}{2} \tan \phi \left( \frac{\theta^3}{3} - \frac{\theta^2 \sin 2\theta}{4} - K \right) \right] + s \left[ K(M_v + wR_1^2) \right. \\
 & + wR_1R_2(\theta^2 \sin \theta + 2n) + \frac{HR_2}{2} \tan \phi \left( \frac{\theta^3}{3} + \frac{\theta^2 \sin 2\theta}{4} + K \right) \left. \right] + \left( s - \frac{CJ}{EI_2} \right) [m(M_v + wR_1^2) \\
 & + nwR_1R_2 + KHR_2 \tan \phi] + KHR_2 \sin \phi \cos \phi \left( 1 - \frac{CJ}{EI_2} \right) \\
 & + mHR_2 \cos^2 \phi \left( \tan \phi + \frac{CJ^2}{EI_2} \cot \phi \right) = 0 \quad . . . . . \quad (13)
 \end{aligned}$$

in which  $K = \frac{\theta \cos 2\theta}{4} - \frac{\sin 2\theta}{8}$ ;  $m = \frac{\theta}{2} - \frac{\sin 2\theta}{4}$ ;  $n = \theta \cos \theta - \sin \theta$ ; and

$$z = \cos^2 \phi + \frac{CJ}{EI_z} \sin^2 \phi.$$

The values obtained by solving equations (12) and (13) are  $H = 10,800$  lb. and  $M_y = -6500$  ft.-lb. Substituting these values in (7), (8), and (9) and



Fig. 6.—The Reinforcement and the Shutters for the Risers.

simplifying, the final equations for the bending and twisting moments on the flights when its ends are fixed are

$$M_{rf} = 22.56 \cos \theta + 21.7\theta \sin \theta - 29.07.$$

$$M_{nf} = -41.8 \sin \theta - 8.1\theta \cos \theta - 10.3\theta.$$

$$T_f = 41.02 \sin \theta - 20.14\theta \cos \theta - 25.66\theta.$$

These quantities are shown by the broken lines in *Fig. 3*.

Substitution of the numerical value for  $H$  in (4), (5), and (6) gives equations for shearing and other forces when the ends of the flight are fixed. These quantities are shown by the broken line in *Fig. 3*. The reinforcement required to resist bending and shearing forces at various sections are calculated by the common methods.

The resistance to torsion of a rectangular member  $T_r$  is given by Saint-Venant as  $\frac{b^3 d^2 q}{1.8b + 3d}$ , and in this case, in which  $b = 8$  in.,  $d = 48$  in., and  $q = 125$  lb. per square inch,  $T_r = 9700$  ft.-lb. The maximum twisting moment  $T_f$  (*Fig. 3*) is 13,000 ft. lb., and extra reinforcement is provided in accordance with the formula given by Prof. W. T. Marshall and Mr. N. R. Tembe. It is clear from the graphs that less reinforcement is used if the stairway is analysed by the second method, the only moments which are greater being the fixing moments at the ends of the flight. Part of the shuttering of the stairway is shown in *Fig. 5* and the arrangement of the reinforcement in *Fig. 6*.

The architects are Messrs. Lionel H. Fewster & Partners. The stairs were designed by the British Reinforced Concrete Engineering Co., Ltd., who collaborated with the author in preparing this article. The general contractors were Messrs. F. G. Minter, Ltd.

(1).—A. H. Mattock. Design and Construction of a Helical Staircase. "Concrete and Constructional Engineering", March, 1957.

(2).—S. Timoshenko and P. M. Lessells, Applied Elasticity. W.T.N.S. Press, Pittsburgh.

## Nomograms for the Design of Beams and Slabs by the Load-factor Method.—II.\*

By J. C. STEEDMAN.

### Rectangular Beams with Reinforcement in Tension and Compression.

NOMOGRAMS Nos. 4A, 4B and 5 on pages 134 to 136 apply to rectangular beams with reinforcement in tension and compression in accordance with the load-factor method as recommended in British Standard Code of Practice No. 114 (1957). The symbols are as used in the Code with the following additions: The percentages of reinforcements in tension and compression are denoted by  $r_{st}$  and  $r_{se}$  respectively. Separate charts are provided for cold-worked bars with  $p_{st} = 30,000$  lb. per square inch and  $p_{se} = 23,000$  lb. per square inch (Nomogram No. 4A); mild-steel bars,  $p_{st} = 20,000$  lb. per square inch and  $p_{se} = 18,000$  lb. per square inch (Nomogram No. 4B); and other combinations of stresses in the reinforcement (Nomogram No. 5). The equations from which the nomograms are derived are

$$\frac{M}{bd_1^2} = \frac{p_{cb}}{4} + \frac{p_{se}r_{se}}{100} \left( 1 - \frac{d_2}{d_1} \right) \quad \text{and} \quad r_{st} = \frac{r_{se}p_{se}}{p_{st}} + \frac{100p_{cb}}{3p_{st}}$$

The method of using the nomograms is explained in the examples which follow, and the operations required in each example are shown on the nomogram.

EXAMPLE No. 4.—A rectangular beam 9 in. wide and 30 in. deep is subjected to a bending moment of 3,000,000 in.-lb. Determine the required cross-sectional areas of reinforcement in tension and compression if  $p_{st} = 30,000$  lb. per square inch,  $p_{se} = 23,000$  lb. per square inch, and  $p_{cb} = 1000$  lb. per square inch. The centre of the reinforcement is 2 in. from each face.

$$\frac{M}{bd_1^2} = \frac{3,000,000}{9 \times 28^2} = 425; \frac{d_2}{d_1} = \frac{2}{28} = 0.072.$$

From Nomogram No. 4A,  $r_{st} = 1.74$  per cent. and  $r_{se} = 0.82$  per cent. Therefore  $A_{st} = \frac{1.74}{100} \times 28 \times 9 = 4.39$  sq. in. and  $A_{se} = \frac{0.82}{100} \times 28 \times 9 = 2.07$  sq. in.

EXAMPLE No. 5.—Calculate the cross-sectional area of reinforcement for the beam in example No. 4 if the stresses are  $p_{st} = 27,000$  lb. per square inch,  $p_{se} = 18,000$  lb. per square inch, and  $p_{cb} = 1250$  lb. per square inch.


$\frac{M}{bd_1^2} = 425$  and  $\frac{d_2}{d_1} = 0.072$  as before. The value of  $p_{se}$  should be compared

with the stress corresponding to the value of  $\frac{d_2}{d_1}$  used and should not be greater than that value. From Nomogram No. 5  $r_{st} \times p_{st} = 5.39 \times 10^4$ ; therefore  $r_{st} = 1.995$  per cent. and  $r_{se} \times p_{se} = 1.21 \times 10^4$  and  $r_{se} = 0.675$  per cent. Therefore


$$A_{st} = \frac{1.995}{100} \times 28 \times 9 = 5.03 \text{ sq. in. and } A_{se} = \frac{0.675}{100} \times 28 \times 9 = 1.70 \text{ sq. in.}$$

(To be continued.)


\*Continued from February number.

No. 4A.—DESIGN OF RECTANGULAR BEAMS BY THE LOAD-FACTOR METHOD.  
Reinforcement in Tension and Compression.

NO. 4B.—DESIGN OF RECTANGULAR BEAMS BY THE LOAD-FACTOR METHOD.  
Reinforcement in Tension and Compression.



No. 5.—DESIGN OF RECTANGULAR BEAMS BY THE LOAD-FACTOR METHOD.  
Reinforcement in Compression and Tension.



## Canadian Views on Concrete in Britain.

SEVENTY engineers and architects from Canada visited this country at the end of January and beginning of February under the auspices of the Cement and Concrete Association, and they attended lectures and demonstrations and visited sites and works in connection with concrete structures in general and precast and prestressed concrete in particular. Some of them gave their opinion on the concrete industry in Britain as follows.

"Building construction in London can hardly be described to be other than fabulous; new office buildings forty stories in height and covering acres, new hotels eighteen stories high, the multitude of housing schemes and new schools, the modern hangars at Gatwick, to name only a few, strike one again of the vitality of the construction industry. In Canada we have regarded the British architect and engineer to be very conservative persons, but this trip has certainly dispelled such false impressions. Our special interest was in precast and prestressed concrete construction. British industry is more advanced in this line than its counterpart in Canada. I have been impressed by the eagerness of the British construction industry to develop new design and construction techniques." (A City Engineer.)

"With the high strengths of concrete and steel now available, the plentiful supply of aggregates in Britain, and rigid control of the product, it now appears that precast and prestressed concrete can compete economically with conventional concrete construction for works having long spans and for construction in inclement weather." (Dean of a Faculty of Engineering and Architecture.)

"In precast concrete, we observe a large variety of roof and floor systems which are basically similar, whereas in Canada we have tended to standardise on the best systems and improve them for a wider use. The general acceptance and wider usage of precast and prestressed concrete in Britain is probably the reason for the larger number of systems available. One of the main reasons to which we attribute this trend is the excellent practical research and training facilities made available by the Cement and Concrete Association. We regret that no comparable facilities are available to the concrete industry as a whole, either in

Canada or the U.S.A. The development of transit mix (ready-mixed) concrete is more advanced in Canada and the U.S.A. than in Britain. This condition may be attributed to a greater congestion of roads, but we feel that the main obstacle is the resistance to changing existing practice. Regarding concrete finishes and the manufacture of precast and prestressed products, we are of the opinion that the Canadian standards of quality are somewhat higher. We are pleased to see the development of economical art work largely in concrete." (President of a precast-concrete Company.)

"The Canadian construction industry has keener competition between the various structural materials available, namely wood, glu-lam (plywood), rolled steel, cast-in-situ, precast and prestressed concrete. Because of the development simultaneously in Canada of all these materials there has been no concerted effort on the whole of the construction industry to explore the design possibilities and in particular the application of precast and prestressed concrete to buildings as has been the case in Britain. Recent works of the London County Council generally are of a strong, vigorous character, dependent on form and texture rather than on colour and shadow for architectural emphasis. Prestressed precast concrete seems further advanced in Britain than in Canada from the standpoint of using space frames, multiple-story buildings, and the more varied use of small prefabricated structural units. Design methods involving new theories, model studies, and computer analysis seem to be used more and be further advanced in Britain." (An architect.)

"In contrast to some new construction techniques, such as the tower crane for high structures, there appears to be a preponderance of hand labour (two men doing one man's job) and a haphazardness in site organisation. The site planning of Roehampton (flats) is superb. As opposed to the distant impressiveness of this project much of the workmanship in finishing left much to be desired compared to standards in Canada. The design of the main building and 'finger' of Gatwick Air Terminal is an excellent piece of architectural design. Details and finishes are consistently well handled throughout." (An architect.)




FIG. 2.—PLAN.




FIG. 3.—CROSS SECTION.  
Car Park at Bristol. (See facing page.)

## A Multiple-story Car Park in Bristol.



Fig. 1.

A PARKING garage (Fig. 1) of six stories is being built at Bristol in the form of a ramp of reinforced concrete supported on reinforced concrete columns and beams and precast piles. The structure is oval on plan, the overall dimensions being about 209 ft. by 129 ft. The ramp is 56 ft. wide. At the centre of the building are two lifts and two staircases by means of which the drivers of the cars will travel to and from the ground floor.

The ramp is supported by columns 1 ft. by 2 ft. in cross section at about 16 ft. centres in the direction of the ramp and in pairs at 32 ft. centres across the ramp. Transverse beams supporting the floor slab span between the columns and cantilever 11 ft. beyond them at both sides of the ramp. Beams in the direction of the ramp are provided only at the inner line of columns at the ends of the building.

The gradient of the ramp at the sides of the building is 1 in 32 and the average gradient at the curved ends is 1 in 46. The ramp has a slope of 1 in 26 towards the inner edge, where rainwater outlets are provided. About 60 per cent. of the area of the ramp will be available for cars and will have a capacity of about 540 cars. A typical plan is shown in Fig. 2, and a typical cross section in Fig. 3.

The ground floor will have two petrol stations and several shops and show-

rooms, one of which will contain a turntable for cars. The joint consulting engineers are Mr. E. N. Underwood and Messrs. G. C. Mander & Partners, the consultant architect is Mr. R. Jelinek-Karl, and the main contractors are Messrs. William Cowlin & Son, Ltd. The structure is being built for a company controlled by Mr. M. Weston, of London.

### Lectures on Building.

THE following lectures have been arranged by the Ministry of Works. Admission is free.

Settlement of Buildings, by S. R. Rosenak. South Dorset Technical College, Newstead Road, Weymouth. March 22; 7.30 p.m.

Work Study in the Building Industry, by K. C. Symons. College of Art, Green Lane, Derby. March 23; 7.15 p.m.

Practical Formwork Design and Construction of Concrete, by J. G. Richardson. College of Technology, Howard Street, Rotherham. March 24; 7.15 p.m.

Prevention of Accidents in the Building Industry, by J. A. Hayward. Cleveland Technical College, Corporation Road, Redcar. March 29; 7.15 p.m.

Prestressed Concrete, by H. Kaylor. Municipal Technical College, Blackburn. March 31; 7.15 p.m.

## FIFTY YEARS AGO.

From "CONCRETE AND CONSTRUCTIONAL ENGINEERING", March, 1910.

## A Retaining Wall 50 ft. High.



A very high retaining wall in Los Angeles is shown in the illustration. "The wall has a length of 600 ft. and is 52 ft. 8 in. high at maximum height, with a minimum of 13 ft. The wall is surmounted by a 5-ft. parapet. The foundation at maximum height of wall is 14 ft. wide; the wall ranges in width from 8 ft. 1 in. to 3 ft. wide at the base of the parapet. The specifications called for construction in 40-ft. sections, no two adjoining sections to be constructed simultaneously. Alternating expansion and contraction joints are provided for. The section method of construction required frequent removal of the contractor's plant and two sets of workmen were employed, one for mixing and spreading concrete, the other on the forms and back-filling the wall with a 6-in. layer of coarse gravel. The concrete of one section was allowed to set before another section was begun. The expansion joints are reinforced with pilasters (at 80 ft. centres). The contraction joints were formed midway between the pilasters."

## Courses for Concrete Gangers.

THREE full-time courses for concrete gangers have been prepared by a joint committee of the London Master Builders Association and the Federation of Civil Engineering Contractors in collaboration with the Cement and Concrete Association. The object of the courses is to provide simple and practical instruction for the concrete ganger or potential ganger. The courses will be conducted by the Cement and Concrete Association at Wexham Springs, Bucks., and each course will occupy two weeks with a break of a fortnight between each week. The first course will be from April 25 to April 29 and May 16 to May 20; the second course is from May 2 to May 6 and May 23 to May 27; and the third course is from May 9 to May 13 and May 30 to June 3.

Details of the courses can be obtained from the Education Department of the London Master Builders Association at 47 Bedford Square, London, W.C.1.

## Design of a Helical Stair

Built in 1908.

THE contractors for the helical stair built in 1908 at the Franco-British Exhibition, and described in our number for January, 1960, were the Yorkshire Hennebique Contracting Co., Ltd.

## THE UNIVERSITY OF LEEDS

## BURSARIES

## IN CONCRETE TECHNOLOGY

Applications are invited for Bursaries in Concrete Technology tenable from 1st October, 1960.

The value of the Bursaries is £400 per annum, out of which the University fees must be paid. The Bursaries will be awarded for one year and may in certain circumstances be renewed for a second year.

Applicants must hold a degree in Engineering, or its equivalent. The course will include post-graduate lectures, design, drawing and laboratory work.

Applications, giving full details of qualifications and experience, together with the names of two referees, must be received by THE REGISTRAR, The University, Leeds, 2, not later than 1st March, 1960.

★ no matter how large  
your formwork or mould  
requirements may be . . .



we can design  
and supply you

#### HARBOUR CONSTRUCTION WORK

Illustration of a block mould being inspected prior to shipment overseas for an important Harbour Construction Contract. This is one of many moulds despatched, and is now producing concrete blocks to a high degree of accuracy.

**STELMO**

the most comprehensive  
mould service in the world



Where  
**CONCRETE**  
is subject to  
**CORROSIVE**  
**ATTACK**

USE

*The Cement for Industry*

Concrete made with Ciment Fondu has a high resistance to many chemicals which are inimical to ordinary concrete. It is invaluable for floors and other constructional work in Dairies, Breweries and Distilleries, Sugar Refineries, Confectionery Manufacture, Meat Plants, Milk Products, Paper Mills, Artificial Silk Factories, Tanneries, Fertilizer Plants, etc.

Write today for  
further particulars  
and latest literature.



**CORROSION-RESISTANT CONCRETE**

**CONCRETE IN HOURS—NOT DAYS**

**REFRACTORY CONCRETE**  
(Using firebrick aggregate)

**HEAT INSULATING CONCRETE**  
(Using light-weight aggregate)

**LAFARGE ALUMINOUS CEMENT COMPANY LIMITED**

73 BROOK STREET, LONDON, W.1. Telephone: MAYFAIR 8346

AP/70

## Precast Ribbed Floor Slabs.

A NEW type of ribbed floor slab has been used in the construction of a three-story office building 228 ft. long by 30 ft. wide for the Atomic Energy Authority at Winfrith Heath, Dorset. The external frame (Fig. 1) includes eighty-eight reinforced concrete columns which were precast in lengths of 33 ft., which is the height of the building.

The floor panels are each 15 ft. by 12 ft., and have ribs in two directions forming 18-in. squares. The total thickness of each panel is 7½ in., which includes the runners for fixing the ceiling and a slab 1½ in. thick. The slab is reinforced with light-weight steel mesh having apertures 3 in. square. Therefore holes for services can be made at any part of the slab between the ribs. Each panel weighs 3½ tons and was lifted by a crane with tackle attached at four points (Fig. 4).

The junction of the panels with the columns is a combination of a mechanical and cast-in-place concrete joint (Fig. 2).

At each floor a strip of steel plate ½ in. thick and 4½ in. deep, and with a 1-in. twisted deformed bar welded to the top and bottom edges, projects 10½ in. from opposite faces of the columns. In the underside of the ribs of the precast panels



Fig. 2.—Connection Between Column and Floor Panel.

there are slots 2 in. to 3 in. wide into which the plates fit when a panel is lowered into position. The weight of the panel is transferred to the plate by direct bearing on suspension bars embedded in the



Fig. 1.—The Frame During Construction.



Fig. 3.—Erecting a Column.

concrete above and at the sides of the slot. The slots are filled with 1 : 1 : 2 concrete which is injected through openings in the 1½-in. slab above the slots. When

the filling has hardened the shearing forces are transmitted partly by bearing and partly by adhesion of the filling. Connections of this type have been tested by applying the equivalent of loads exceeding the total dead and imposed load on one side and the dead load only on the other side.

The columns are at intervals of 12 ft. in four rows along the length of the building. Each outer row is 12 ft. from the inner rows, which are 6 ft. apart. Each floor panel is supported by four columns (Figs. 1 and 3) and cantilevers 3 ft. beyond the columns in the inner rows, thereby forming half the floor of the central corridor.

The stairs comprise separate precast members of inverted L-shape which were placed by one man on to a pair of beams, which form the up-stand carrying the balustrade.

The time taken for the erection of the precast frame was twenty-five days. It is claimed that a column can be erected in twenty minutes, and a floor slab in ten minutes, by lifting them directly from a lorry and placing them in their final position. The designer of the structure was Mr. Stephen Revesz, and the main contractors were the Turriff Construction Corporation, Ltd. The Modular Concrete Co., Ltd., were the contractors for the reinforced concrete work and also made the precast members.




Fig. 4.—Erecting a Floor Slab.

## Gateway Flats, Dover



Client: Dover Corporation. Architects: Dalgliesh & Patten, F.R.I.B.A. Consultants for Civil Engineering Work: S. H. & D. E. White

This important structure is supported by 1152 piles 17" in diameter and up to 30 feet long.

The frame is of reinforced concrete throughout, and as far as practicable, beams were precast. Staircases, balcony slabs, and panels were also precast, thus effecting considerable economies in formwork costs for these members. Wind frames, of multi-bay, multi-storey, fixed portal type, are incorporated in the design to withstand the maximum exposure condition of the British Standard Code of Practice, in view of the exposed nature of the site beside the English Channel.

The Scheme is of exceptional length—1400 feet overall—and lying below Dover Castle it forms a striking addition to the historic water-front.

R

RUSH & TOMPKINS LIMITED

T

BUILDING & CIVIL ENGINEERING CONTRACTORS  
SIDCUP • LONDON • BURBANK • EDMONTON, ALBERTA



THE  
**TUNNEL**

**PORTLAND CEMENT COMPANY LIMITED**



— manufacturers of the finest Portland cements, provide a comprehensive service covering most areas of Great Britain. Strategically-placed depots backed by a modern road transport fleet ensure rapid deliveries.



*Head Office:*  
105 PICCADILLY, LONDON, W.1  
*Telephone:* Grosvenor 4100

## Large Bored Foundation Piers.

A U.S.A. machine for drilling foundation piers was used for the first time in this country on the site of a 16-story office building now being erected in Euston Road and Gower Street, London. The machine (Fig. 1) comprises a chassis, with hydraulic stabilising jacks, surmounted by a retractable jib 78 ft. long which is in a horizontal position during transit.

At the position of each pier the machine is levelled by the jacks and the jib is raised to a vertical position. Within the jib is a square steel kelly-bar which is rotated by means of a rotatable table operated by a diesel engine. A hard-steel auger of the diameter required is attached to the bottom of the kelly-bar by a quick-release pin, and when it is rotated it bores into the ground at a speed depending on the hardness of the material. The auger is raised to the surface at short intervals, and by a rapid rotational movement the excavated material is flung off the blades and falls around the perimeter of the hole (Fig. 2). When the hole has been drilled to the depth required the auger is replaced by an under-cutting tool, which flares out the bottom of the hole to a greater diameter, thus providing an increased bearing area for the pier. Upon completion of the boring operation reinforcement, if required, is lowered into the hole and the entire excavation is filled with concrete up to the level of the underside of the pile-cap or other foundation structure. The machine can drill holes up to 8 ft. diameter to great depths and the rate of boring, which depends on the size of the auger, may be several feet per minute.

At the Euston Road and Gower Street site there are 145 piers of diameters from



Fig. 2.

21 in. to 60 in., and penetrating to 60 ft. into firm London clay. Reinforcement is provided in the top of the larger piers to act as splice-bars. In the smaller piers reinforcement is provided from the top to within 20 ft. of the bottom. A steel lining-tube was used temporarily at the top of each hole to support the gravel which overlies the clay. Ready-mixed concrete was used as the main contractors' mixing plant had not been erected.

The machine was operated by McKinney Foundations, Ltd., who are associated with Messrs. John Laing & Son, Ltd., the main contractors for the building.



Fig. 1.

**"Towards the Robot."**

MR. R. M. AMODIA comments as follows on the "Editorial Notes" in our number for January, 1960.

Very rightly, you have condemned the trend towards over-specialisation at the cost of broader outlook and liberal education. In my view, the outlook of industry is much more responsible for this trend. It is apparent, for example, that a man working on, say, steel structures finds it difficult to get employment on concrete design, and a man working on highways finds it difficult to get employment on water-supply and sewerage schemes. What else could be the outcome if not over-specialisation?

This attitude does create robots, and, in the long run, robots without real efficiency.

[A Robot is a machine in the form of a man in which are installed mechanisms that enable it to perform certain functions, but it cannot think for itself. Our article was a plea that men should be educated so that they can think logically as well as apply automatically the principles and formulae that have been instilled into them at a technical school. At present this is seldom the case, as this and other articles published in this journal have clearly shown. The evil is not confined to civil and structural engineering. We have frequently quoted the misgivings of leaders of other professions on the lack of education and general knowledge of technologists. "The Builder" for January 22, 1960, page 164, quotes a report emanating from the Welsh School of Architecture in which it is stated that the students are in general of a lower standard of education than is required in any comparable profession and often behave like children, and that the staffs often perform functions for which they are not qualified.

Specialisation to-day is unavoidable, but this is no reason why specialists should not be educated men and women capable of logical thought and of an appreciation of the arts. We suggest that our correspondent, and others in a like position, make a serious effort to realise that their work is part only of their lives, and endeavour to widen their interests in intellectual matters by making their friends among people engaged in other pursuits.—ED.]

**Plastic Lining for Column Shutters.**

THE illustration shows the column shutters used in the construction of a bridge on the St. Albans by-pass road. The columns are 14 ft. high and 4 ft. 6 in. diameter, and were concreted to the full height in four hours with the aid of a skip



on a mobile crane. The timber is lined with polystyrene plastic sheet made by Monsanto Chemicals, Ltd., in order to produce a smooth surface. The shutters are removed twenty-four hours after the concrete is cast, and concrete does not adhere to the lining. The contractors are Messrs. Holland & Hannen and Cubitt, Ltd.

**IMPERIAL COLLEGE OF  
SCIENCE AND TECHNOLOGY**


*Bursaries in Concrete Technology*

Bursaries of £460-£760 according to experience are available for Session 1960-61. Candidates must hold a degree in engineering and have a good knowledge of the theory of structures. Full information from the Registrar, Imperial College, London, S.W.7.

Closing date, June 1st, 1960.

March, 1960.

# Multi-wire strand For prestressed concrete



This photograph shows the stressing of multi-wire "Bridge" Strand at the Perth Narrows Bridge in Australia. "Bridge" Strand is made from Somerset Wire.

**CONSULTING ENGINEERS:** G. Maunsell & Partners  
**PRESTRESSED CONCRETE CONSULTANT:** E. W. H. Gifford  
**CONTRACTORS:** Christiani & Nielsen Ltd.

**IF YOU WANT TO PUT STEEL INTO CONCRETE  
GET IN TOUCH WITH**

## **GKN Reinforcements Ltd**

**197 KNIGHTSBRIDGE, LONDON, S.W.7. KENSINGTON 6811**

**SMETHWICK, BIRMINGHAM** (Smethwick 1991) • **MANCHESTER** (Ardwick 1691)  
**GLASGOW** (Bell 2444) • **MIDDLESBROUGH** (3843) • **CARDIFF** (Cardiff 45220)  
**BRISTOL** (Bristol 21555) • **LEICESTER** (Leicester 25114) • **LEEDS** (Leeds 27311)  
 WORKS AT CARDIFF, SMETHWICK, WIGAN & GLASGOW

## MISCELLANEOUS ADVERTISEMENTS.

**Situations Wanted, 5d. a word : minimum, 12s.** **Situations Vacant, 6d. a word : minimum, 15s.** **Other miscellaneous advertisements, 6d. a word : minimum, 15s.** **Displayed advertisements, 40s. per column inch.** **Box number 1s. extra.**

Advertisements must reach this office, 14 Dartmouth Street, London, S.W.1, by the 23rd of the month preceding publication.

## SITUATIONS VACANT.

**SITUATIONS VACANT.** Air Ministry Works Designs Branch requires in London structural engineering designer draughtsmen for reinforced concrete or structural steel-work of all types. Applicants must have adequate training and several years' experience. Some site experience and possession of recognised technical qualification an advantage. Financial assistance and time off may be allowed for recognised courses of study. Promotion and pension prospects. Five-days' week with 18 working days leave per year initially. Salary for Grade III ranges from £680 (at age 25) to £900 per annum. Commencing salary dependent on age, qualifications and experience. Also vacancies in higher grade for suitably qualified candidates on range from £905 to £1,055 per annum. Applicants who must be natural born British subjects, should write to Air Ministry, W.G.C., London House, Theobalds Road, London, W.C.1, or to any Employment Exchange (quotient Order No. King's Cross 3745) giving age, details of training, qualifications, full particulars of former posts held and copies of any testimonials. Candidates selected will normally be interviewed in London and certain expenses reimbursed.

**SITUATIONS VACANT.** South London consulting engineers require experienced reinforced concrete engineers, designer-draughtsmen, and detailers. Applicants should have a minimum experience of three years in position applied for. Salary commensurate with experience and ability. Luncheon vouchers, and five-days' week. Please write, giving details of age, qualifications, and experience, to LEONARD & GRANT, 344 South Lambeth Road, London, S.W.8.

**SITUATIONS VACANT.** Consulting engineers have vacancies for reinforced concrete detailers, and designer-detailers. Salaries in accordance with experience. Luncheon vouchers. Apply in writing to BYLANDER, WADDELL & PARTNERS, 169 Wembley Park Drive, Wembley, Middlesex.

**SITUATIONS VACANT.** Civil Engineering Assistants required for site work on contracts. The work is varied and interesting with opportunities for promotion and study of new methods. Applicants should be between the ages of 26 and 32, and hold a degree in civil engineering or equivalent. They should have had a minimum of 3 years with a contractor on site work, which must have included setting-out and progress measurement. Experience in design of formwork and other temporary works, control of concrete quality would be an advantage. Apply in writing, giving brief details of qualifications and experience, also stating age, and salary required, to THE CHIEF ENGINEER, THE DEMOLITION & CONSTRUCTION CO. LTD., 3 St. James's Square, London, S.W.1.

**SITUATIONS VACANT.** Junior Civil Engineers required to work on sites with excellent opportunities for training. Applicants should be graduates or equivalent and should be between the ages of 20 and 26. Apply in writing, giving brief details of qualifications and experience (including vacation course work), also stating age, to THE CHIEF ENGINEER, THE DEMOLITION & CONSTRUCTION CO. LTD., 3 St. James's Square, London, S.W.1.

**SITUATION VACANT.** Engineering assistant experienced in the design of reinforced concrete bridges and other structures, capable of supervising drawing office staff. Salary range £945-£985 per annum. Superannuation fund. Reduced rates of travel, and other concessions. Five-days' week. Applications, giving qualifications and experience, to CHIEF CIVIL ENGINEER, Western Region of British Railways, Paddington Station, London, W.2.

**SITUATIONS VACANT.** Assistant engineers, steelwork designer-draughtsmen, reinforced concrete designer-detailers, and detailer-draughtsmen required for varied and interesting work on structures for industrial, commercial, medical, and residential buildings. Five-days' week. Luncheon vouchers. Apply, with details of experience, and salary required, to JOHN F. FARQUHARSON & PARTNERS, Chartered Structural Engineers, 34 Queen Anne Street, London, W.1. Telephone Langham 6081.

**SITUATIONS VACANT.** Small structural engineering office, London, W.C.1 area, with extensive practice, requires additional assistants. Capable men from graduateship upwards required for high-class miscellaneous work generally, foundations, dangerous structures, steel, concrete and timber, and able to work with minimum supervision. Reply in confidence, with full particulars, and salary required, to Box 4634, CONCRETE AND CONSTRUCTIONAL ENGINEERING, 14 Dartmouth Street, London, S.W.1.

**SITUATIONS VACANT.** Reinforced concrete designers and detailers required. Minimum three years' practical experience on structural work. Good salary and prospects for right men. Written applications to JOHN LIVERSIDGE & ASSOCIATES, 43 Portland Place, London, W.1.

**SITUATIONS VACANT.** Reinforced concrete engineers require reinforced concrete designer-detailer and detailing draughtsmen for reinforced concrete work. Write, giving age, experience, and salary required, to CONSIDERE CONSTRUCTION LTD., 72 Victoria Street, London, S.W.1.

**SITUATION VACANT.** Prestressed concrete supervisor wanted by well-established company for works on western outskirts of London. Applicant must have wide experience of various systems, and be able to deal with all aspects of labour utilisation, production and quality control. The post is pensionable, and offers excellent prospects to the right man. Existing staff have been notified of the vacancy. Please write, giving in confidence, full details of experience, age, and salary required, to Box 4649, CONCRETE AND CONSTRUCTIONAL ENGINEERING, 14 Dartmouth Street, London, S.W.1.

**SITUATIONS VACANT.** Senior reinforced concrete designer/detailers and experienced detailers required in Hammersmith office of consulting engineers. High salaries and good prospects, with interesting work. Five-days' week, pension scheme. Apply, in confidence, with full details of experience, and salary required, to ALAN MARSHALL & PARTNERS, Federal House, 2 Down Place, London, W.6. Telephone Riverside 8772.

**SITUATIONS VACANT.** Consulting engineer, Westminster, invites applications from detailer/draughtsmen with a minimum of four years' experience in reinforced concrete. Salary scales appropriate to experience and ability. Non-contributory pension and bonus schemes in operation. Holiday arrangements will be honoured. Apply in writing, giving full particulars, to Box 4650, CONCRETE AND CONSTRUCTIONAL ENGINEERING, 14 Dartmouth Street, London, S.W.1.

**SITUATIONS VACANT.** Designer/detailers for reinforced concrete. Experience in civil engineering an advantage. Salary according to qualifications and experience. Luncheon vouchers are provided. Apply, in writing, to HUSBAND & CO., Consulting Engineers, 70 Victoria Street, London, S.W.1.

**SITUATIONS VACANT.** Civil engineering department of THE COFFEE CO. (G.B.) LTD., 140 Piccadilly, London, W.1, require reinforced concrete designers and detailers for wide variety of industrial structures. Steelwork experience additional advantage in one of the positions to be filled. Five-days' week. Pension scheme in operation. Write, stating age, experience, and salary required.

**SITUATIONS VACANT.** Designer/detailers and detailers required in an expanding reinforced concrete design office for work on all types of structures and civil engineering projects. A good standard of draughtsmanship is essential. Pension scheme. Salary/bonus commensurate with ability. MALCOLM GLOVER & PARTNERS, Consulting Engineers, Terminal House, London, S.W.1. Telephone Sloane 6442 and 7734.

**SITUATION VACANT.** Draughtsmen widely experienced in design of special and standard steel shoring and allied builders' equipment. Concrete mould experience an advantage. Write, giving full details of experience and qualifications, to Box 4654, CONCRETE AND CONSTRUCTIONAL ENGINEERING, 14 Dartmouth Street, London, S.W.1.

**WATES LTD.****REINFORCED CONCRETE  
DESIGNER/DETAILERS**

Vacancies occur in our Engineering Department for Designer/Detailers and Detailers on interesting reinforced concrete work, both in-situ and precast. Previous experience with specialist firm in this field is desirable, but not essential. Working conditions are first class. There is a profit-sharing bonus scheme after a probationary period, five-days' week, superannuation scheme, and subsidized canteen. Positions are progressive and offer excellent experience to energetic men interested in developing up-to-date techniques of design and construction. Salary ranging from £700 to £1100 per annum according to experience.

Please apply in writing, stating age, training, experience and present salary, to: PERSONNEL MANAGER, 1360 London Road, Norbury, London, S.W.16.

**SITUATIONS VACANT.** Reinforced concrete detailers and designers required in North West London. Three-weeks' paid holiday, and excellent prospects in small expanding firm. Telephone Maida Vale 7390.

**SITUATION VACANT.** Senior detail draughtsman required for detailing reinforced and prestressed concrete structures. Preferably with five years' experience of this or similar work. Age 25-30. Pension, superannuation and bonus schemes in operation. Apply to THE HOVERINGHAM CONCRETE CO. LTD., Hoveringham, Notts.

**SITUATION VACANT.** Junior draughtsman required for detailing reinforced and prestressed concrete structures. Age 18-22. Apply to THE HOVERINGHAM CONCRETE CO. LTD., Hoveringham, Notts.


**AGENTS**

are required for senior appointments on large construction contracts in various parts of the country.

Applicants will be required to have a sound experience on a wide variety of contract work. L.I.O.B. or A.M.I.C.E. qualifications preferred. Age 30-40.

These appointments offer progressive and permanent employment with superannuation scheme.

Salary will be commensurate with experience and qualifications.

Apply in writing to PERSONNEL MANAGER (A.5), JOHN LAING AND SON LIMITED, London, N.W.7.



**Experienced  
Reinforced  
Concrete  
Designer / Detailers  
and Draughtsmen  
Wanted  
for our Stafford,  
London & Provincial  
Design Offices**

**Apply**

*Chief Engineer: A. P. MASON,  
B.Sc., M.I.C.E., M.I.Struct. E., M.ASCE.*  
**THE BRITISH REINFORCED CONCRETE  
ENGINEERING CO. LTD., STAFFORD**

**SITUATION VACANT.** Young man required as cement and concrete tester at site near Waltham Abbey. Duties to include testing of cement, concrete aggregates, and plastic and set concrete. Preference will be given to an applicant with either some previous experience or general experience of laboratory work, but training would be given to the chosen applicant if necessary. Please reply to Box 4651, CONCRETE AND CONSTRUCTIONAL ENGINEERS, 14 Dartmouth Street, London, S.W.1.

**SITUATION VACANT.** Young engineer, age 30-35, wanted. Must be thoroughly conversant with the design and use of specialised formworks for in-situ and precast concrete. This position requires a person capable of dealing with complete schemes from client level to production level of the designed equipment at our works. Send details of experience, and salary required, to Box 4653, CONCRETE AND CONSTRUCTIONAL ENGINEERS, 14 Dartmouth Street, London, S.W.1.

**SITUATIONS VACANT.** Structural and civil engineers required for their Bristol office senior and intermediate designer-detailers experienced in either (1) reinforced concrete, or (2) structural steelwork. Excellent opportunities in an expanding organisation for the right men. Positions are pensionable, and offer first-class experience. Box 4659, CONCRETE AND CONSTRUCTIONAL ENGINEERS, 14 Dartmouth Street, London, S.W.1.

**SITUATION VACANT.** Senior engineer required for London professional office. Must have professional qualifications and at least five years' design experience in structural reinforced concrete. Knowledge of steelwork an advantage. Age limit 30-40. Candidates should be capable of handling contracts from start to finish and able to control staff. The work is varied and offers scope for initiative. A good salary will be offered. Apply, stating experience, and salary required, to FAAMEN & DARK, Romney House, Tufton Street, Westminster, S.W.1.



# STONE \* COURT AGGREGATES



General View of Plant at Richmond Park.

## ONE OF OUR MODERN CONCRETE AGGREGATES PLANTS


First-Class Washed graded concrete aggregates, and shingles for road dressing, coupled with efficient delivery, are at the service of contractors and Municipal Authorities in London, Berks, Bucks, Herts, and Middlesex Areas.

Our products include Washed Sharp Sand, all sizes of shingles, from  $3/16''$  up to  $2''$ , either crushed or natural.

Special Specifications made to order.

**STONE COURT BALLAST CO. LTD.**  
PORTLAND HOUSE, TOTHILL ST., WESTMINSTER, S.W.1.

Telephone : Abbey 3456.



GLASGOW

NEWCASTLE

BELFAST

LEEDS

LIVERPOOL

MANCHESTER

DUBLIN

LEICESTER

STAFFORD

BIRMINGHAM

CARDIFF

BRISTOL

LONDON

*Specialists in Reinforced Concrete Design and Suppliers of Reinforcement, with Design and Branch Offices strategically placed throughout the British Isles*

*The BRC service includes a Site Investigation Department*

**REINFORCED CONCRETE IS CONSTRUCTION AT ITS BEST**

There are vacancies for experienced engineers in several of our design offices.

*The British Reinforced Concrete Engineering Co. Ltd., Head Office & Works: Stafford*

10-11, 2312

Published by CONCRETE PUBLICATIONS LTD., 14 Dartmouth Street, London, S.W.1. Telephone: Whitehall 4381  
Printed by BUTLER & TANNER LTD., The Selwood Printing Works, Frenze and London